


VICINITY MAP



BUCKEYE MUNICIPAL AIRPORT TAXIWAY & SOUTH APRON RECONSTRUCTION PHASE II

FAA AIP NO. 3-04-0005-026-2023

A PORTION OF THE NORTH-EAST CORNER OF SECTION 20, TOWNSHIP 1N, RANGE 4W OF THE GILA & SALT RIVER BASE & MERIDIAN, MARICOPA COUNTY, ARIZONA.





OWNER

BUCKEYE MUNICIPAL AIRPOR' JEFF WEBBE 3000 S PALO VERDE RD BUCKEYE, AZ 85326 623-349-6880 JWEBBE®BUCKEYEAZ.GOV

ENGINEER

DIBBLE
DUANE DANA, P.E.
1640 S STAPLEY DR, STE 120
MESA, AZ 85204
480-757-7876
DUANE.DANA@DIBBLECORP.COM

BASIS OF BEARING SHEET INDEX HORIZONTAL DATUM: NAD83 (2011 Epoch) ARIZONA CENTRAL ZONE REFER TO SHT GG1.01

VERTICAL DATUM:

BENCH MARK

POINT NUMBER 31
FOUND PUBLISHED BENCHMARK DESCRIBED AS:
BUCKEYE MUNICIPAL ARPORT CONTROL. POINT 'A' (SAC)
BRASS CAP FLUSH.
GRO NORTHING = 803423.85
GRID EASTING = 4655.561
PUBLISHED ELEVATION = 1118.495

<u>A</u>	~~~
1ST REVISED APPROVAL	
DISCLAIMER:	
THE CITY APPROVES THESE PLANS FOR CONCEPT ONL NO LIABILITY FOR ERRORS AND OMISSIONS.	LY AND ACCEPTS
BY: Start	04/12/2023
CITY OF BUCKEYE ENGINEER	DATE
BY: BY EMAIL	03/29/2023
FEDERAL AVIATION ADMINISTRATION	DATE

AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE "AS — BUILT" INFORMATION SHOWN HEREON WAS OBTAINED UNDER MY DIRECT SUPERVISION AND IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ARIZONA REGISTERED LAND SURVEYOR	DATE
ARIZONA REGISTRATION NUMBER	
TELEPHONE NUMBER	

RECEIVED 04/04/2023 CITY OF BUCKEYE by: NV



MANAGING ENGINEERING / SURVEYOR	DUANE DANA, P.E.	PROJECT COORDINATOR	JEFF WEBBE	DESIGN LAYOUT DRAFTED CHECKED	MJH MJH		FIELD SURVEY DRAFTED CHECKED	JPG JLB JPG	DRAWING SCALES	SEE PLANS	
PLAN TYPE		Į de			ENGINEER INFORMATION						
PROJECT:	(IST REVISED)	BUCKEYE MUNICIPAL AIRPORT TAXIWAY & SOUTH APRON RECONSTRUCTION PHASE II			COB PROJECT PLAN STICKER	ENGCIP-22-0001	Airport Taxiway & S. Apron Reconstruction Ph2	Revised Plan Set	Sheets: 68	2R - FOR SIGNATURE	
Е	BUCKEY	ΈM	UNICI	PA	L AIF	RPC	RT	G	T ID: 31.0	0	
SNO	<u></u> A F	REPAC	KAGE	- 03	30/20	23					
REVISIONS	2										
CC	B PERMITT PROVED S	ING EAL		CC	B ENG	INEE D SF	RING		Г		-026-2023
"		OVE)						;	<u>t</u>	<u> </u>
	04/12/2023								1	bmitta	Ö

CITY OF BUCKEYE ENGINEERING 04/22/2022 03/30/2023 1 of 67 1018028.05

GENERAL PERMITTING NOTES

AND/OR PLANS ARE OBTAINED. ALL OF THESE REQUIREMENTS APPLY TO ONSITE GRADING AND IMPROVEMENT PLANS.

UTILITY (COMPANIES
-----------	-----------

DATE SUBMITTED

ELECTRIC	ARIZONA PUBLIC SERVICE	4/17/19
TELEPHONE	CENTURYLINK	4/16/19

VICINITY MAP NOT TO SCALE



GENERAL PERMITTING NOTES

- GENERAL PERMITTING NOTES

 1. ALL CONSTRUCTION IN THE PUBLIC RIGHTS-OF-WW OF IN EXSEMENTS
 ASSOCIATION OF GOVERNMENTS (MAG) UNIFORM STANDARD SPECIFICATIONS AND
 UNIFORM STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION AS AMENDED
 BY THE LATEST VERSION OF THE CITY OF BUDICEY EXESTS MANDARDS. IF
 OF THE CITY PERMITS (MAG) UNIFORM STANDARD SPECIFICATIONS AND
 UNIFORM STANDARD DETAILS FOR PUBLIC WORKS CONSTRUCTION AS AMENDED
 BY THE LATEST VERSION OF THE CITY OF BUDICEY EXPERITED THE ARE
 OF THE CITY PERMITS SENDED WITHIN ONE (1) YEAR. THE PLANS
 OF THE CITY PERMITS SENDED WITHIN ONE (1) YEAR. THE PLANS
 AND THE PUBLIC PERMITS WITHIN ONE (1) YEAR. THE PLANS
 AND THE PUBLIC PERMITS WITHIN ONE (1) YEAR. THE PLANS
 BY THE CITY OF THE OWNER OF THE PUBLIC P

UTILITY COMPANIES


DATE SUBMITTED

ELECTRIC	ARIZONA PUBLIC SERVICE	4/17/19
TELEPHONE	CENTURYLINK	4/16/19

BUCKEYE MUNICIPAL AIRPORT TAXIWAY & SOUTH APRON RECONSTRUCTION PHASE II

FAA AIP NO. 3-04-0005-025-2022

A PORTION OF THE NORTH-EAST CORNER OF SECTION 20, TOWNSHIP 1N, RANGE 4W OF THE GILA & SALT RIVER BASE & MERIDIAN, MARICOPA COUNTY, ARIZONA.



STORM WATER DRAINAGE CERTIFICATE

ALL DRAINAGE DESIGN WILL COMPLY WITH THE CITY OF BUCKEYE CURRENT GRADING AND DRAINAGE DESIGN STANDARDS.



OWNER

CITY OF BUCKEYE
JUSTIN GOODERE
530 E MONROE AVE,
BUCKEYE, AZ 85326
623-349-6275
JGOODERE@BUCKEYEAZ.GOV

ENGINEER

DIBBLE
DUANE DANA, P.E.
7878 N 16TH ST, STE 300,
PHOENIX, AZ 85020
602-957-1155
DUANE.DANA@DIBBLECORP.COM

BASIS OF BEARING SHEET INDEX

HORIZONTAL DATUM: NADB3 (2011 Epoch) ARIZONA CENTRAL ZONE

VERTICAL DATUM:

REFER TO SHT GG1.01

BENCH MARK

POINT NUMBER 31
FOUND PUBLISHED BENCHMARK DESCRIBED AS:
BUCKEYE MUNICIPAL AIRPORT CONTROL POINT 'A' (SAC)
BRASS CAP FLUSH.
GRID NORTHING = 883423.85
GRID EASTING = 46545.61
PUBLISHED ELEVATION = 1118.495

APPROVAL

THE CITY APPROVES THESE PLANS FOR CONCEPT ONLY AND ACCEPTS NO LIABILITY FOR ERRORS AND OMISSIONS.

05/12/2022 DATE

02/08/2022 DATE BY: BY EMAIL
FEDERAL AVIATION ADMINISTRATION

AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE "AS — BUILT" INFORMATION SHOWN HEREON WAS OBTAINED UNDER MY DIRECT SUPERVISION AND IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ARIZONA REGISTERED LAND SURVEYOR


ARIZONA REGISTRATION NUMBER

TELEPHONE NUMBER

RECEIVED MAY 11 2022 CITY OF BUCKEYE by: RL



YOR				CHECKE	머		CHECKE	JPG				
RING / SURVE	DUANE DANA, P.E.	TOR	JUSTIN GOODERE	DRAFTED	МЛН		DRAFTED	JLB			SEE PLANS	
MANAGING ENGINEERING / SURVEYOR	DUANE	PROJECT COORDINATOR	TSUC	DESIGN LAYOUT	WITH		FIELD SURVEY	JPG		DRAWING SCALES	35	
PLAN TYPE					ENGINEER INFORMATION							
PROJECT:		BUCKEYE MUNICIPAL AIRPORT TAXIWAY &	SOUTH APRON RECONSTRUCTION PHASE II		COB PROJECT PLAN STICKER	ENGCIP-22-0001	CIP - Airport Taxiway & South Apron Reconstruction Ph 2	100% Final Improvement Plan	Sheets: 57	2R - FOR REVIEW		
-	BUCKEY	Έľ	MUNICI	PA	-	RPC	DRT	SHI	GG	ID: 1.00		
SNO	⚠ F	EP/	ACKAGE	- 03	/30/2	023						
A REVISIONS	3 B PERMITT PROVED SI	ING		cc	B ENG	SINEE	RING					022
(APPRO 04/12/ DITY OF B ENGINE	OVE 202 BUCI ERI	3	DE	AI M/ CITY EN	OF E	OVEI 2 202 BUCK ERII	22		SUBNZHA Submittal	SUBMITTAL	1-0005-025-2
PR	IGINAL PLA 04/22/20 0JECT NUI	022 MBEI	2 R	١.	TEST I	REVIS	ATE NA SISSION I	DATE		COB PLAN TRACKING #	COB PERMIT # ENGCIP-22-0001	FAA AIP NO. 3-04-0005-025-2022
1	01802	8.0	5	ľ,	1A)	C	of	57		8	8 亩	JLL.



- CITY OF BUCKEYE BUILDING DEPARTMENT SHALL BE NOTIFIED 24 HOURS IN ADVANCE OF ANY ON-SITE OR OFF SITE CONSTRUCTION. PHONE 623-349-6248 FOR THE HOTLINE. ALL OTHERS FAX THE INSPECTION REQUEST FORM TO 623-349-621, OR USE THE WEB BASED PERMIT PORTAL ACCESS TO SCHEDULE AN INSPECTION (WWW BUCKEYEAZ GOV).
- ALL WORK AND MATERIALS MUST CONFORM WITH THESE SPECIFICATIONS, THE CURRENT UNIFORM STANDARD SPECIFICATIONS AND DETAILS FOR PUBLIC WORKS CONSTRUCTION AS SPONSORED AND DISTRIBUTED BY THE MARICOPA ASSOCIATION OF GOVERNMENTS (M.A.G.) AND AS AMENDED BY THE CITY OF
- 3. A PERMIT IS REQUIRED FROM THE TOB FOR ALL CONSTRUCTION WITHIN THE RIGHTS-OF-WAY (ROW).
- 4. THE CONTRACTOR WILL EXPOSE ALL EXISTING UTILITY LINES BEING TIED IN TO VERIFY THEIR LOCATION.
- 5. THE CONTRACTOR WILL LOCATE, OR HAVE LOCATED, ALL EXISTING UNDERGROUND UTILITIES (ELECTRIC, TELEPHONE, PIPELINE, ETC.) AND STRUCTURES IN ADVANCE OF CONSTRUCTION AND WILL ELIMINATE ALL CONFLICTS PRIOR TO START OF CONSTR CONSTRUCTION.
- THE CONTRACTOR IS RESPONSIBLE TO CALL BLUE STAKE PRIOR TO STARTING ANY CONSTRUCTION. NO WORK SHALL BEGIN UNTIL BLUE STAKE IS COMPLETED. BLUE STAKE TELEPHONE NUMBER 602–263–1100 OR 1–800–5TAKE—IT.
- A PRE-CONSTRUCTION MEETING IS REQUIRED PRIOR TO STARTING ANY WORK OR NEW PHASE OF WORK. THE CONTRACTOR, KEY SUB-CONTRACTORS, TOB INSPECTOR AND REPRESENTATIVE OF THE TOWN ENGINEER SHALL ATTEND THIS MEETING.
- 8. ANY WORK PERFORMED WITHOUT THE APPROVAL OF THE TOB AND/OR ALL WORK AND MATERIAL NOT IN CONFORMANCE WITH THE SPECIFICATIONS IS SUBJECT TO REMOVAL AND REPLACEMENT AT THE CONTRACTOR'S EXPENSE.
- 9. DISPOSAL OF EXCESS MATERIAL WITHOUT A PERMIT WITHIN THE TOE LIMITS IS PROBREMED. A LISE FERMING SEQUEDED FREMENDED OF STORYGUND OF MATERIAL SITTING WITHING SETTING META. STOR DISPOSAL OF STORYGUND OF MATERIAL SHALL NOT EXCEED A SHEEKING META. STORYGUND OF THE STORYGUND FROM SHALL NOT EXCEPT OF THE STORYGUND EXCAVATED MATERIAL SHALL NOT EXCEED A 4:1 RATIO OF LENGTH TO HEIGHT.
- 10. EXCAVATION CONTRACTORS MUST IDENTIFY LOCATION FOR DISPOSING OF EXCESS EXCAVATION MATERIAL ALONG WITH A LETTER FROM THE LAND OWNER, GIVING PERMISSION FOR DIMPING PRIOR TO STARTING ANY CONSTRUCTION.
- PERMISSION TO UNMINIS FROM TO STARTING AND CONSTRUCTION.

 1. TRAFFIC CONTROL SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND THE CITY OF PHOENIX (COP) BARRICADING MANUAL, MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION, MAG UNIFORM STRADARD DETAIL 401, AND TOB REQUIREMINTS. THE CONTRACTOR SEQUENCE TO SUBMIT A WHERE THE CONSTRUCTION OF THE NEW IMPROVEMENTS ARE ADJACENT TO OR CONNECTING TO ANY EXISTING ROADWAY OR PEDESTRIAN FACILITIES. THE TRAFFIC CONTROL PLAN AND BARRICADE PLAN SHALL BE APPROVED BEFORE A PERMIT FOR THE WORK WILL BE ISSUED. THE CONTROLOR SHALL INSURED. HE FOR THE WORK WILL BE ISSUED. THE CONTROLOR SHALL INSURED.
- 12. A HAUL PLAN FOR MATERIAL IMPORT OR EXPORT SHALL BE REQUIRED FOR TOB REVIEW AND APPROVAL PRIOR TO THE START OF HAULING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAILY AND FINAL CLEAN-UP OPERATIONS OF ADJACENT, EXISTING PAYED STREETS USED BY CONSTRUCTION TRAFFIC. THIS WORK INCLUDES STREET SWEEPING, POWER BROOM AND WATER AS NEEDED OR DIRECTED BY THE TOB.

13. ENVIRONMENTAL REQUIREMENTS

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR DUST CONTROL RELATED TO THE PROJECT CONSTRUCTION AND SHALL TAKE WHATEVER MEANS NECESSARY TO CONTROL ANY ABNORMAL CONDITIONS.
- THE CONTRACTOR SHALL PROVIDE ADEQUATE MEANS FOR CLEANING TRUCKS AND/OR OTHER EQUIPMENT OF MUD PRIOR TO ENTERING PUBLIC STREETS, AND TAKE WHATEVER MEASURES ARE NECESSARY TO INSURE THAT ALL ROADS ARE MAINTAINED IN A CLEAN, MUD AND DUST FREE CONDITION AT ALL TIMES.
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAILY AND FINAL CLEAN—UP OPERATIONS OF ADJACENT, EXISTING PAVED STREETS USED BY CONSTRUCTION TRAFFIC.
- TEMPORARY DRAINAGE CONTROL MEASURES MAY BE REQUIRED DURING AND AFTER CONSTRUCTION UNTIL FINAL PROJECT BUILD-OUT IN ACCORDANCE WITH THE APPROVED PLANS AND IN ACCORDANCE WITH ANY ESTABLISHED OR REQUIRED BEST MANAGEMENT PRACTICES (BMP) AS PART OF THE NATIONAL POLLUTION DISCHARGE ELMINATION SYSTEM (NPDES) PERMIT REQUIREMENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MEET ALL REQUIREMENTS.
- E. THE CONTRACTOR IS RESPONSIBLE TO OBTAIN ALL AIR QUALITY PERMITS.
- F. THE CONTRACTOR SHALL SUBMIT TO THE TOB A COPY OF THEIR APPROVED COUNTY (AIR QUALITY) DUST CONTROL PLAN, EROSION CONTROL PLAN (SWPPP), AND PERMIT PRIOR TO THE START OF WORK.
- 4. STREET CUTS: APPLICATIONS FOR STREET CUT PERMITS MUST BE APPROVED BY THE TIOWN ENGINEER PROPERTY OF APPROVAL OF IMPROVEMENT PLANS THERE TENDERS LOCATED IN A RESINING PAULE STREET SHALL BE CONSTRUCTED IN ACCORDANCE M.A.G. UNIFORM. STRANDARD DETAIL NO. 200 "T"—TOP. BACKFILL PAVEMENT SUFFACE REPLACEMENT, MODIFIED AS FOLLOWS: THE WIDTH OF THE REPLACED PAVEMENT SECTION EXTEND 1 FOOT BEYOND THE TRENCH SIDE EDGE LINE, ON EITHER SIDE OF THE TRENCH SIDE FOR THE PERMANENT.

CITY OF BUCKEYE GENERAL NOTES (CONT'D)

- LY OF BUCKEYE GENERAL NOTES (CONTO)

 SURFACE REPLACEMENT SHALL BE A MINIMUM OF 3 INCHES OR MATCH THE
 EXISTING THICKNESS OF THE PAVENENT, WHICHEVER IS GREATER. SAWCUT OR
 CONSTRUCTION JOINTS SHALL BE ADEQUATELY TACK OLDED WITH A MINIMUM OF
 95% COVERAGE, ASPHALT MATERIAL SHALL BE A TOB APPROVED MIX DESIGN
 WITH COMPACTED LIFTS NO GREATER THAN 3 INCHES, SURRY BACKFILLED OR
 OPEN TRENCHES IN EXISTING ROADWAYS MUST BE PROPERLY STEEL PLATED
 AND BARRICADED OVER NIGHT STEEL PLATES TO BE MILLED FLUSH WITH
 ROADWAY SURFACE PER NOTE 24. "COLD MIX" TEMPORARY ASPHALT PATCHES
 MUST BE REPLACED AS SOON AS POSSIBLE AND CANNOT REMAIN FOR MORE
 THE CONTRACT DIS SECURIED TO LIFT THE DURING THEM DEP MORE
 THE CONTRACT DIS SECURIED TO LIFT THE THE PROPERTY SEED LIFT AND OVERLAYED AS MINIMUM OF 20 FEET PAST TERNCH WALLS, AND IN THE
 CASE OF MULTIPLE STEED CLUTS, THE CONTINUOUS MILL AND OVERLAY SHALL
 EXTEND A MINIMUM OF 2 FEET PAST FENCH WALLS.
- 15. POTHOLING: NO POTHOLING SHALL BE DONE ON ANY STREET NEWER THAN 2 YEARS OLD. ALL POTHOLING IN EXISTING STREETS SHALL BE DONE USING WAITER/AIR/ACCIUM TYPE METHOD. POTHOLE SIZE SHALL BE LIMITED TO A 12 NICH BY 12 NICH SQUARE HOLE. REMOVAL MATERIAL CANNOT BE USED FOR BACKHLI. THE CONTRACTOR SHALL USE SULRRY PER MAG SEC. 728. PAVEMENT REPLACEMENT SHALL BE BY APPROVED HOT MIX ASPHALT ONLY. A 3 FOOT SHALL BE BY APPROVED HOT MIX ASPHALT ONLY. A 3 FOOT SHALL BE SHAPPED BY AFTER THE ASPHALT IS PLACED.
- 16. AN APPROVED, UP-TO-DATE SET OF PLANS AND A RIGHT-OF-WAY PERMIT SHALL BE MAINTAINED ON THE JOB SITE AT ALL TIMES WHILE WORK IS IN PROGRESS, IF THE PLANS AND PERMITS ARE NOT ON SITE, THE WORK SHALL BE STOPPED UNTIL THE APPROVED PLANS ARE PROVIDED. DEVATION FROM THE PLANS SHALL NOT BE ALLOWED WITHOUT THE TOB'S APPROVAL
- 17. DAMAGE TO ANY AND ALL ITEMS CAUSED BY CONSTRUCTION OR CONSTRUCTION RELATED WORK SHALL BE REPLACED OR REPAIRED TO THE SAME OR BETTER CONDITION AT THE CONTRACTOR'S EXPENSE.
- 18. ALL PARCEL CONSTRUCTION ACCESS LOCATIONS ARE SUBJECT TO THE TOWN ENGINEER'S APPROVAL. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING PROPER AND ADEQUATE ACCESS ROADS INSIDE AND THROUGHOUT THE PARCEL ALLOWING FOR INSPECTION ACCESSIBILITY. THIS INCLUDES GRADING, GRAVEL FILL AND/OR TRENCH PLATES AS REQUIRED.
- 19. THE CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE COUNTIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT INCLUDING SAFETY OF ALL PRESONS AND PROPERTY. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR SHALL DEFEND, INDEMINEY AND HOLD THE TOB AND THE TOB CONSULTANTS HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THE SPENDING FOR USED THE TOB.
- 20. THE TOB SHALL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES UTILIZED IN CONNECTION WITH THE WORK. THE TOB WILL NOT BE RESPONSIBLE FOR THE CONTRACTOR'S FAILURE TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS COMPLYING WITH MAG OR TOB REQUIREMENTS.
- 21. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING CERTIFIED AS-BUILT RECORD DOCUMENTS TO THE TOB FOR REVIEW AND APPROVAL. NO FINAL RECORD DOCUMENTS TO THE TOB FOR REVIEW AND APPROVAL. NO FINAL ACCEPTANCE SHALL BE ISSUED UNTIL "AF-BUILT" PLANS CERTIFIED BY THE PROJECT ENGINEER/LAND SURVEYOR HAVE BEEN SUBMITTED AND ACCEPTED BY THE TOB. FINAL CONSTRUCTION ACCEPTANCE OR THE RELEASE OF CERTIFICATE OF OCCUPANCIES SHALL NOT BE ISSUED UNTIL ALL AS-BUILT DRAWINGS AND OTHER REQUIRED DOCUMENTS PER THE TOB'S FINAL PROJECT SUBMITTAL CHECKLIST, HAVE BEEN REVIEWED AND APPROVED BY THE TOWN ENGINEER.
- 22 ARRANGEMENTS FOR CONSTRUCTION WATER CAN BE MADE BY CALLING THE WATER RESOURCE DEPARTMENT AT (623) 349-6800.
- THE TOB IS NOT RESPONSIBLE FOR LIABILITY ACCRUED DUE TO DELAYS AND/C DAMAGES TO UTILITIES IN CONJUNCTION WITH THIS CONSTRUCTION. ALSO, THE TOWN WILL NOT PARTICIPATE IN THE COST OF CONSTRUCTION OR RELOCATION OF UTILITIES.
- 24. ALL CONTRACTORS SHALL CONTRACT FOR TRASH PICKUP THROUGH A LICENSED TOWN OF BUCKEYE SOLID WASTE HAULER (602-237-2078) AND DISPOSED OF AT THE SOUTHWEST REGIONAL LANDFILL IN BUCKEYE.
- 25. OPEN TRENCHES ACROSS DRIVEWAYS, STREETS AND CROSS-STREETS SHALL BE PLATED FOR OVERNIGHT, WEEKEND OR EXTENDED PERIODS, PER M.A.G. UNIFORM STANDARD DETAIL 211.
- 26. ALL ABC SHALL BE FROM AN ARIZONA DEPARTMENT OF TRANSPORTATION (ADOT) APPROVED SOURCE LIST.
- 27. LONGITUDINAL TRENCH BACKFILL IN EXISTING ARTERIAL, COLLECTOR, OR LOCAL ROADWAYS OR ADJACENT TO EXISTING ROADWAY (WHEN THE TRENCH EXCAVATION FALLS WITHIN 2 FEET OF EDGS OF PAWEMENT) SHALL REQUIRE 1/2 SACK CLSM PER MAG SPEC 728 FULL DEPTH OR ABC FULL DEPTH AS DIRECTED BY THE TOB. AGC BACKFILL COMPACTION SHALL BE BY AN APPROVED MECHANICAL
 - TOB. ABC BACKFILL COMPACTION STALL BE BY AN APPROVED MECHANICAL METHOD (NO WATER SETTLING) WITH BACKFILL MATERIAL LETS AS FOLLOWS:

 12 INCH LETS (LOOSE) TO BE USED IN THE TOP 4 FEET OF THE TRENCH

 24 INCH LETS (LOOSE) TO BE USED FROM 1 FOOT OVER THE PIPE TO 4 FEET FROM THE TOP 0° THE TRENCH PER MAG SEC. 601.4.
- 28. ALL BACKFILL WITHIN OR ADJACENT TO EXISTING ROADWAYS SHALL BE MECHANICALLY COMPACTED.
- TRANSVERSE TRENCH BACKFILL IN ALL EXISTING ROADWAYS SHALL REQUIRE 100% FULL DEPTH HALF SACK CLSM PER MAG SPEC 728.
- 30. ALL MATERIAL SUBMITTALS INCORPORATED IN THE PROJECT SHALL BE SUBMITTED AT OR BEFORE THE PRE-CONSTRUCTION MEETING FOR REVIEW AND APPROVAL AT OR BEFORE THE PRE-BY THE TOWN ENGINEER.

GENERAL NOTES

- ALL CONSTRUCTION TO CONFORM THE LATEST REVISIONS OF THE MARICOPA ASSOCIATION OF GOVERNMENTS (MAG) STANDARD SPECIFICATIONS AND DETAILS UNLESS SPECIFICATIONS AND DETAILS UNLESS SPECIFICATION WITH THE FEDERAL AVAITON ADMINISTRATION (FAA) ADVISIONY CIRCULARS (AC) AS IDENTIFIED AND SPECIFIED WITHIN THE PLANS AND CONTRACT DOCUMENTS.
- 2. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN, AT THEIR OWN EXPENSE, SUCH PERMITS AS ARE REQUIRED FROM THE APPROPRIATE AGENCIES.
- 3. ANY WORK PERFORMED WITHOUT THE KNOWLEDGE AND APPROVAL OF THE ENGINEER AND/OR OWNER AND ALL WORK MATERIALS NOT IN CONFORMATION WITH THE PLANS AND SPECIFICATIONS IS SUBJECT TO REMOVAL AND REPLACEMENT AT THE CONTRACTOR'S SOLE EXPENSE.
- 4. NO JOB WILL BE CONSIDERED COMPLETE UNTIL ALL OFFSITE CURBS, PAVEMENT AND SIDEWALKS HAVE BEEN SWEPT CLEAN OF ALL DIRT AND DEBRIS, AS WELL AS ALL PAVEMENT WITHIN THE AIR OPERATIONS AREA (AOA).
- THE CONTRACTOR SHALL KEEP SUITABLE EQUIPMENT ON HAND AT THE JOBSITE FOR MAINTENANCE OF DUST CONTROL, AND SHALL CONTROL DUST AS DIRECTED BY THE APPROPRIATE AGENCIES, AS WELL AS ANY FOREIGN OBJECT DEBRIS (FOD) WITHIN
- 6. A THOROUGH ATTEMPT HAS BEEN MADE TO SHOW THE LOCATION OF ALL UNDERGROUND DESTRUCTIONS AND UTILITY LINES IN THE WORK AREA. THE ENGINEER AND THE OWNER WILL NOT GUARANTEE ANY LOCATIONS OR ELEVATIONS. EFF EXISTING LUNGERGROUND UTLITIES SUMMAN IN THESE FLAMS. THE CONTRICTOR STANDARD ST SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING IN THEIR VICINITY.
- THE CONTRACTOR IS REQUIRED TO CONTACT THE AIRPORT A MINIMUM OF TWO WORKING DAYS (48 HOURS) PRIOR TO COMMENCEMENT OF CONSTRUCTION FOR A UTILITY LOCATE. THE APPROPRIATE UTILITY COMPANIES SHALL BE NOTIFIED BY THE CONTRACTOR PRIOR TO ANY CONSTRUCTION.
- 8 ALL CHANTITIES SHOWN ON PLANS ARE APPROXIMATE ARE NOT VERIFIED BY THE OWNER, AND ARE FURNISHED SOLELY FOR THE CONTRACTOR'S CONVENIENCE
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN COPIES OF M.A.G STANDARDS AND SPECIFICATIONS AS WELL AS ALL OTHER FEDERAL STANDARDS AND SPECIFICATIONS NECESSARY TO COMPLETLETY AND ACCURATELY INTERPRET THESE
- 10. CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT ALL EXISTING AIRPORT FACILITIES, INFRASTRUCTURE, AND IMPROVEMENTS, INCLUDING TENANT FACILITIES. ANY DAMAGE CAUSED BY CONTRACTOR SHALL BE REPLACED OR REPHARED BY CONTRACTOR AT THEIR SOLE EXPENSE TO THE SATISFACTION OF BOTH THE ENGINEER AND THE OWNER OF THE DAMAGED PROPERTY.
- 11. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING WHICH SHALL BE PERFORMED BY A REGISTERED LAND SURVEY IN THE STATE OF ARIZONA.
- 12. THE OWNER MAY ORDER ANY OR ALL WORKMANSHIP AND MATERIALS TO BE TESTED ACCORDING TO APPLICABLE STANDARDS.
- 13. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE COST OF ALL REWORK AND/OR REMOVAL. AND REPLACEMENT OF ALL MATERIALS AND/OR WORKMANSHIP REPRESENTED BY A FALING TEST.
- 14. APPROVAL OF A PORTION OF THE WORK IN PROGRESS DOES NOT GUARANTEE ITS FINAL ACCEPTANCE, TESTING AND EVALUATION MAY CONTINUE UNTIL WRITTEN FINAL ACCEPTANCE OF A COMPLETE AND WORKABLE UNIT.
- 15. THE OWNER MAY SUSPEND THE WORK BY WRITTEN NOTICE WHEN, IN ITS JUDGEMENT, PROGRESS IS INDASTISFACTORY, WORK BEING DONE IS UNAUTHORIZED OR DEFECTIVE, WEATHER CONDITIONS ARE UNSUITABLE, OR THERE IS A DANGER TO THE PUBLIC HEALTH OR SAFETY.
- STREET AND TRAFFIC SIGNS WILL BE RELOCATED BY THE CONTRACTOR. IF NECESSARY, AT THE DIRECTION OF THE OWNER.
- 17. CONTRACTOR IS RESPONSIBLE FOR QUALITY CONTROL TESTING.
- 18. THE CONTRACTOR SHALL COMPLY WITH THIS PROJECT'S CONSTRUCTION SAFETY AND PHASING PLAN AT ALL TIMES.
- 19. THE CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN ALL EXISTING AIRPORT ACCESS GATES AND FENCING USE BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN THE SECURITY OF SAID ACCESS GATES AND FENCING AND PROVIDE TEMPORARY FENCES (MIN. 6" HIGH) AS NEEDED. ANY DAMAGE TO THE AIRPORT'S EXISTING FENCE AND GATES SHALL BE SATISFACTORILY REPAIRED OR REPLACED TO A CONDITION EQUAL TO OR BETTER THAN THE ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE CONTRACT.

REVISIONS TO THE PROPERTY OF	E - 03/30/2023			
PLAN NAME				
GE	NERAL NOTES			
ENGINEER INFORMATION	DIBBLE			
				23)
COB PERMITTING APPROVED SEAL	COB ENGINEERING APPROVED SEAL			20
APPROVED	APPROVED	<u> </u>	<u> </u>	ဖ
04/12/2023	MAY 12 2022	1		8
CITY OF BUCKEYE ENGINEERING	CITY OF BUCKEYE ENGINEERING	SUBMITTAL:	ziid our	0005
AS-BUILT SEAL	DESIGN SEAL	S		4
ORIGINAL PLAN DATE	47425 DAMA DAMA H. DAM	RACKING #	,22.0001	4 P NO 3-0


BUCKEYE MUNICIPAL AIRPORT GG1.02

04/12/2023 CITY OF BUCKEYE ENGINEERING	MAY 12 2022 CITY OF BUCKEYE ENGINEERING	DIATTAL:
IS-BUILT SEAL	DESIGN SEAL THE ISSUE OF THE I	ACKING #
ORIGINAL PLAN DATE 04/22/2022	DATEST REVISION BATE 03/30/2023	AN TO

HEET NUMBER 3 of 67

1018028.05





Single-way, (1) - 2" Conduit, Concrete Encased

BASE BID

100% ESTIMATED QUANTITIES

BASE BID 100% ESTIMATED QUANTITIES ITEM No. AS-BUILT QTY. QTY. DESCRIPTION ELECTRICAL 39 1-110-5.3 Multiple-way (2) - 2" Conduit Concrete Encased 75 LF 40 L-115-5.1 New L-867D 16" Diameter Junction Can w/ Blank Cove EA New L-858(L) Size 1, 3-Module, Airfield Guidance Sign, on New Concret 41 L-125-5.2 EA New Elevated L-861T(L) LED Taxiway Edge Light and Isolation Transform 42 L-125-5.4 FΔ on New L-867 Base Can 43 L-125-5.6 Re-Install Salvaged Retroreflective Taxiway Edge Marke EA New Elevated L-861T(L) LED Taxiway Edge Light and Isolation Transfe with Stems, Frangible Couplings and Cords (Spares) 44 1-125-5.7 EA

ADDITIVE ALTERNATE NO. 1

14 EA

New L-853 Retroreflective Taxiway Edge Marker

45 L-125-5.8

·····

	100% ESTIMATED QUANTITIES								
LINE No.	ITEM No.	APPROX. QTY.	UNIT	AS-BUILT QTY.					
		CIVIL							
1	C-100-14.2	Contractor Quality Control Program (CQCP) (Add Alt No. 1)	1	LS					
2	C-102-6.2	Storm Water Pollution Prevention Plan (Add Alt No. 1)	1	LS					
3	C-105-6.2	Mobilization (Add Alt No. 1)	1	LS					
4	GTP-10.01.2	Location of Underground Utilities (Add Alt No. 1)	1	LS					
5	GTP-20.05.2	Airfield Safety and Security (Add Alt No. 1)	1	LS					
6	GTP-30.01.1	Remove, Salvage and Store Aggregate Shoulder Protection	1,216	SY					
7	GTP-30.02.1	Remove 24" X 36" Elliptical Corrugated Metal Pipe (CMP)	86	LF					
8	GTP-30.02.2	Remove Culvert End Structures	2	EA					
9	GTP-40.01.1	Pre-Emergent Herbicide (2 Applications)	1,708	SY					
10	GTP-40.02.1	Crushed Aggregate Shoulder Protection	854	SY					
11	GTP-40.03.1	Crushed Aggregate Underlain with Geosynthetic Filter Fabric	40	SY					
12	GTP-40.04.1	Riprap Underlain with Geosynthetic Filter Fabric (DS0 = 9-Inch, T = 24-Inch)	24	SY					
13	P-101-5.1	Sawcut Asphalt Concrete Pavement (2.5 to 5-Inch Depth)	270	LF					
14	P-101-5.2	Mill Asphalt Concrete Pavement (2.5 to 5-Inch Depth)	2,994	SY					
15	P-152-4.1	Unclassified Excavation	3,500	CY					
16	P-152-4.2	Over-Excavation and Replacement of Unsuitable Materials, Backfill and Compaction	350	CY					
17	P-152-4.3	Compacted Subgrade (6-inch Depth)	3,029	SY					
18	P-152-4.4	Compacted Subgrade (8-inch Depth)	854	SY					
19	P-208-5.2	Crushed Aggregate Base Course (6-Inch Depth)	3,029	SY					
20	P-401-8.1	Bituminous Surface Course (FAA 3/4", 4-Inch Thickness)	3,029	SY					
21	P-620-5.1	Obliterate and Seal Pavement Markings	620	SF					
22	P-620-5.2	Permanent Pavement Markings (Yellow)	730	SF					
23	D-701-5.3	30-Inch x 19-Inch Storm Drain Class V RGRCP	89	LF					
24	D-751-5.4	Mitered Concrete Headwall w/Grate (Inlet)	1	EA					
25	D-751-5.5	Mitered Concrete Headwall w/Grate (Outlet)	1	EA					
26	T-901-5.1	Seeding	1.2	AC					

LINE	ITEM	APPROX.		AS-BUILT	
No.	No.	DESCRIPTION	QTY.	UNIT	QTY.
		ELECTRICAL			
27	L-100-5.1	Remove and Salvage Taxiway Edge Light and Isolation Transformer, Remove Base Can	9	EA	
28	L-100-5.3	Excavate and Remove Existing Conduit & Conductor	795	LF	
29	L-100-5.4	Remove and Salvage Unlighted Airfield Guidance Sign, Remove Concrete Pad	1	EA	
30	L-100-5.5	Excavate and Remove Existing Pull Box / Junction Can	2	EA	
31	L-108-5.1	L-824, Type C, 1/C #8 AWG, 5kV Cable	2,170	LF	
32	L-108-5.2	L-824, Type C, 2/C #8 AWG, 5kV Cable	550	LF	
33	L-110-5.1	Single-way, (1) - 2" Conduit, Slurry Encased	2,010	LF	
34	L-110-5.2	Single-way, (1) - 2" Conduit, Concrete Encased	100	LF	
35	L-110-5.3	Multiple-way, (2) - 2" Conduit, Concrete Encased	115	LF	
36	L-115-5.1	New L-867D 16* Diameter Junction Can w/ Blank Cover	4	EA	
37	L-125-5.1	New L-858(L) Size 1, 2-Module, Airfield Guidance Sign, on New Concrete Sign Base	1	EA	
38	L-125-5.2	New L-858(L) Size 1, 3-Module, Airfield Guidance Sign, on New Concrete Sign Base	1	EA	
39	L-125-5.3	New L-858(L) Size 1, 4-Module, LED Airfield Guidance Sign, on New Concrete Sign Base	1	EA	
40	L-125-5.4	New Elevated L-861T(L) LED Taxiway Edge Light and Isolation Transformer on New L-867 Base Can	8	EA	
41	L-125-5.5	New Elevated L-861T Quartz Taxiway Edge Light and Isolation Transformer on New L-867 Base Can	20	EA	
42	L-125-5.7	New Elevated L-861T(L) LED Taxiway Edge Light and Isolation Transformers with Stems, Frangible Couplings and Cords (Spares)	1	EA	

EARTHWORK QUANTITIES

NOTE: THE FOLLOWING RAW, UNADJUSTED, IN-PLACE EARTHWORK QUANTITES ARE PROVIDED FOR BIDDING PURPOSES. EXCESS EXCAVATION IS STOCKPILED ON SITE AS SHOWN ON SHT GG1.06.

BASE BID ADD ALT
4,940 CY CUT
140 CY FILL
530 CY FILL

BID PACKAGE QUANTITIES

THE BASE BID CONTAINS A TAXIMAY TRANSITION WHICH WILL NOT BE CONSTRUCTED IF THE ADDITIVE ALTERNATE IS AWARDED. THE PLANS SEPARATE THE TRANSITION QUANTITIES FROM THE BASE BID QUANTITIES. THE QUANTITIES PROVIDED FOR BIDDING PURPOSES ON THIS SHEET SHOW THE COMBINED SUM OF THE PLAN QUANTITIES FOR EACH LINE ITEM.

IF THE ADDITIVE ALTERNATE IS AWARDED THE TAXIMAY TRANSITION SHALL NOT BE CONSTRUCTED. THE ADDITIVE ALTERNATE QUANTILES ON THE PLANS ARE UNADJUSTED AND NOT ACCOUNT FOR THE OMISSION OF THE TRANSITION. THE QUANTITIES PROVIDED FOR BIDDING PURPOSES ON THIS SHEET SHOW THE PLAN QUANTITIES FOR EACH LINE ITEM LESS THE QUANTITIES FOR THE TRANSITION, WHICH ARE MEASURED FOR PAYMENT AS PART OF THE BASE BID.


Е	UCKEYE MUNICIPAL AIRPORT	SHEET ID: GG1.04
S	REPACKAGE - 03/30/2023	
REVISIONS	2	
æ	<u></u>	
PL	AN NAME	


PROJECT QUANTITIES


ENGINEER INFORMATION DIBBLE





COR PERMITTING OR ENGINEERING APPROVED APPROVED 04/12/2023 MAY 12 2022 CITY OF BUCKEYE ENGINEERING CITY OF BUCKEYE ENGINEERING AS-BUILT SEAL 04/22/2022 03/30/2023 HEET NUMBER 1018028.05 5 of 67



















































































ELECTRICAL DEMOLITION GENERAL NOTES:

- WITHIN AREAS OF DEMOLITION, AND AS OTHERWISE SHOWN, CAREFULLY REMOVE IDENTIFIED LIGHT FIXTURES, BASES, ISOLATION TRANSFORMERS, HAND HOLES AND OTHER INDICATED ITEMS.
- 2. CABLE REMOVAL
 - A. <u>DIRECT BURIAL:</u> REMOVE FROM WITHIN MANHOLES AND HANDHOLES AND REMOVE IN AREAS WHERE EXCAVATION REQUIRES DISTURBING.
- B. IN CONDUIT: REMOVE COMPLETELY BETWEEN NEAREST BASES, HANDHOLES OR MANHOLES.
- C. <u>RUNWAYS</u>: REMOVE AND REPLACE FOR RECONNECTION INCREMENTALLY DURING EACH SHIFT TO MAINTAIN CIRCUIT OPERATION AS REQUIRED BY AIRPORT.
- AT INDICATED DEVICES TO BE REMOVED OR IN DEMOLITION AREAS INDICATED, REMOVE ALL CONDUCTORS BACK TO NEAREST FIXTURE BASE OR HANDHOLE OUTSIDE DEMOLITION AREA.
- 4. FIXTURES, CABLES, CONDUITS, DUCTS, ETC. WHICH ARE NOT SPECIFICALLY INDICATED TO BE REMOVED (OR WHICH ARE SHOWN TO REMAIN WITHIN AREAS OF GENERAL DEMOLITION) SHALL REMAIN IN-PLACE AND FUNCTIONAL.
- CONTRACTOR SHALL VERIFY EQUIPMENT AND CABLE DESIGNATIONS AND STATUS PRIOR TO REMOVAL OR DISCONNECTING.
- ALL REMOVED LIGHT FIXTURES, BASES, ISOLATION TRANSFORMERS, AND SIGNS SHALL BE SALVAGED AND DELIVERED TO BUCKEYE MUNICIPAL AIRPORT OPERATIONS AND MAINTENANCE. ALL OTHER REMOVED MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE AND PROPERLY DISPOSED OF IN ACCORDANCE WITH LOCAL ORDINANCES.
- DRAWINGS MAY NOT DETAIL ALL EXISTING FACILITIES IN AREAS OF DEMOLITION. CONTRACTOR SHALL REVIEW THE SITE AND RECORD DRAWINGS TO VERIFY THE DEMOLITION EFFORT INVOLVED.
- CONTRACTOR SHALL BE REQUIRED TO HAVE A PRIVATE "ON-SITE" UTILITY LOCATING COMPANY AND POTHOLE EXISTING UTILITY LINES AS NEEDED.

ELECTRICAL LEGEND

E1.2 ELECTRICAL NOTES AIRFIELD ELECTRICAL DEMOLITION PLAN BASE BID - SHEET 1 E2.1 E2.2 AIRFIELD ELECTRICAL DEMOLITION PLAN BASE BID - SHEET 2

E2.3 AIRFIELD ELECTRICAL DEMOLITION PLAN BASE BID - SHEET 3 AIRFIELD ELECTRICAL DEMOLITION PLAN ADD ALT - SHEET 1 E2.4

E3.1 AIRFIELD ELECTRICAL PLAN BASE BID - SHEET 1 F3 2 AIRFIELD ELECTRICAL PLAN BASE BID - SHEET 2

E3.3 AIRFIELD ELECTRICAL PLAN BASE BID - SHEET 3 E3.4 AIRFIELD ELECTRICAL PLAN ADD ALT - SHEET 1

E4.1 AIRFIELD GUIDANCE SIGN SCHEDULE E5.1 DUCTBANK DETAILS E5.2 GROUNDING DETAILS

F1 1

JUNCTION CAN DETAILS E5.3 F5.4 AIRFIELD GUIDANCE SIGN DETAIL AND 5KV SPLICE AIRFIELD GUIDANCE SIGN CONCRETE BASE DETAILS

E5.5 E5.6 ELEVATED EDGE LIGHTING DETAILS E6.1 EQUIPMENT DATA TABLES SHEET 1

EQUIPMENT DATA TABLES SHEET 2 E6.2 AIRFIELD LIGHTING VAULT - ELECTRICAL SITE PLAN E7.1 AIRFIELD LIGHTING VAULT - ELECTRICAL EQUIPMENT DEMOLITION PLAN E7.2

E7.3 AIRFIELD LIGHTING VAULT - ELECTRICAL EQUIPMENT DEMOLITION ELEVATIONS E7.4 AIRFIELD LIGHTING VAULT - MODIFIED ELECTRICAL EQUIPMENT PLAN

E7.5 AIRFIELD LIGHTING VAULT - MODIFIED ELECTRICAL EQUIPMENT ELEVATIONS

E7.6 L-821 LIGHTING CONTROL PANEL SCHEMATIC DIAGRAM E7.7 MODIFIED PANEL A SCHEDULE

ELECTRICAL ABBREVIATIONS:

1/C SINGLE CONDUCTOR 2/C TWO CONDUCTORS

APS ARIZONA PUBLIC SERVICE ATS AUTOMATIC TRANSFER SWITCH

RCC BARE COPPER CONDUCTOR (GROUND)

CCR CONSTANT CURRENT REGULATOR

CE CONCRETE ENCASED

CKT CIRCUIT

СОММ COMMUNICATIONS

DIA DIAMETER

FAA FEDERAL AVIATION ADMINISTRATION

GND GROUND

GRS

GALVANIZED RIGID STEEL (CONDUIT)

LED LIGHT EMITTING DIODE LF LINEAR FEET

NPI NON-PAY ITEM

PVC POLY-VINYL CHLORIDE SE SLURRY ENCASED

SES SERVICE ENTRANCE SECTION

SGN SIGN TYP TYPICAL

SELECTED FAA ADVISORY CIRCULARS FOR AIRPORT PROJECTS: (LATEST VERSION)

150/5340-18	STANDARDS FOR AIRPORT SIGN SYSTEMS
150/5340-30	DESIGN & INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS
150/5345-7	SPECIFICATION FOR L -824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS
150/5345-26	SPECIFICATION FOR L -823 PLUG AND RECEPTACLE, CABLE CONNECTORS
150/5345-42	SPECIFICATION FOR AIRPORT LIGHT BASES, TRANSFORMER HOUSINGS, JUNCTION BOXES, AND ACCESSORIES
150/5345-43	SPECIFICATION FOR OBSTRUCTION LIGHTING EQUIPMENT
150/5345-44	SPECIFICATION FOR RUNWAY AND TAXIWAY SIGNS
150/5345-46	SPECIFICATION OF RUNWAY AND TAXIWAY LIGHT FIXTURES
150/5345-47	SPECIFICATION FOR SERIES TO SERIES ISOLATION TRANSFORMERS FOR AIRPORT LIGHTING SYSTEMS
150/5345-53	AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM
150/5370-2	OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION
150/5370-10	STANDARDS FOR SPECIFYING CONSTRUCTION OF AIRPORTS

ELECTRICAL SCOPE OF WORK:

- TAXIWAY J LIGHTS AND SIGNS WITH NEW HOMERUN CABLE
- 2. NEW CONSTANT CURRENT REGULATOR
- 3. NEW L-821 CONTROL PANEL

ELECTRICAL LEGEND:

(UNLESS OTHERWISE NOTED ON PLANS)

PVC W/#8-5kV L-824 TYPE "C" CABLE PER INDICATED LIGHTING CIRCUIT. (QUANTITY AND SIZE AS INDICATED ON PLAN SHEETS)

Δ

--- EXISTING ELECTRICAL CONDUIT AND CONDUCTOR ---- EXISTING COMMUNICATIONS CONDUIT AND CABLE

> HH/0 EXISTING HANDHOLE

4

JB EXISTING SIZE 5 JUNCTION BOX

EXISTING ELEVATED TAXIWAY EDGE LIGHT

(4) EXISTING TAXIWAY EDGE RETROREFLECTIVE MARKER

EXISTING AIRFIELD GUIDANCE SIGN 0 NEW L-867-D JUNCTION CAN NEW AIRFIELD GUIDANCE SIGN

NEW L-861T QUARTS ELEVATED TAXIWAY EDGE LIGHT ON NEW L-867 BASE

 \bigcirc NEW L-861T(L) LED ELEVATED TAXIWAY EDGE LIGHT ON NEW L-867 BASE

SALVAGED TAXIWAY EDGE RETROREFLECTIVE MARKER





CITY OF BUCKEYE

•		CATHERINE ALCORN HA
٦.	ORIGINAL PLAN DATE	LATEST REVISION DA
1	04/22/2022	03/30/2023
	PROJECT NUMBER	SHEET NUMBER
	1018028.05	35 of (



ELECTRICAL CONSTRUCTION PHASING NOTES

- CONTRACTOR SHALL COORDINATE ALL WORK WITH AIRPORT MAINTENANCE, AIRPORT OPERATIONS, AND THE ENGINEER AS NECESSARY.
- CONTRACTOR SHALL GIVE 72 HOURS NOTICE PRIOR TO WORKING ON OR AROUND ANY DUCTBANKS, HANDHOLES, ETC.
- CONTRACTOR SHALL MAINTAIN OR HAVE SUFFICIENT MATERIAL/ EQUIPMENT REQUIRED TO PROVIDE TEMPORARY LIGHTING AND CIRCUIT EXTENSIONS. THIS INCLUDES, BUT IS NOT LIMITED TO FIXTURES, TRANSFORMERS, BASES, COMDUIT, L-824 CABLE & L-823 SPLICE KITS. THESE ITEMS WILL NOT BE AVAILABLE FROM THE BUCKEYE MAINTENANCE SHOP.
- 4. THE CONTRACTOR SHALL MAINTAIN QUALIFIED PERSONNEL WITH THE APPROPRIATE EQUIPMENT, FOR THE INSTALLATION AND SPLICING OF ARRIELD LIGHTING. SUCH PERSONNEL SHALL BE CAPABLE OF 60 MINUTE RESPONSE TIME IF THEY ARE NOT ALREADY PRESENT ON THE
- 5. TURN OFF AND COVER EXISTING SIGNAGE THAT MAY POTENTIALLY MISDIRECT AIRCRAFT IORN OF AND COVER EXISTING STORAGE THAT MAY POTENTIALLY MISDIRECT AIRCRAFT MOVEMENT INTO CLOSED AREAS BARRICADE FOR CONSTRUCTION. SIGNAGE REQUIRING PARTIAL COVERAGE WITH TAXIMAY LOCATION PANELS REMAINING VISIBLE SHALL REMAIN ON WITH ONLY DIRECTIONAL PORTIONS COVERED WITH SECTIONS OF DARK COLORED TARPO OR DOUBLE-LAYERD BURLAP THAT DOES NOT PERMIT VISIBILITY OF COVERED PORTION OF ARRAY DAY OR NIGHT. COVERS SHALL BE SECURELY HELD IN PLACE BY RATCHETING LASHING STRAPS, NO TAPE OR ADHESIVES WILL BE PERMITTED. SEE PHASING PLANS FOR PLACEMENT OF SIGN COVERS.
- COVER EXISTING ELEVATED EDGE LIGHT FIXTURES IN CLOSED AREA BARRICADED FOR CONSTRUCTION WITH 4" PVC PIPE. COVER SHALL EXTEND 2" MIN. ABOVE TOP OF FIXTURE.
- 7. PROVIDE ANY TEMPORARY AIRFIELD CIRCUIT JUMPERS REQUIRED TO MAINTAIN OPERATION OF FRUNDER AND LEMPORATE AMPRILLET RUCCUIT JUMPERS NEGURED DE MANINATO PERSONATOR OF CONCUENT JUMPERS SECURED TO ACCURED TO THE PROPERTY OF THE PROPERTY CIRCUIT JUMPERS MAY BE ROUTED THROUGH NEW TAXIMAY CROSSINGS OF EXISTING SPARE CONDUITS. AS ROUTED AND THROUGH NEW TRAINATY CROSSINGS OF EXISTING SPARE CONDUITS AND SOURIED AND SHALL BE COMPLETELY REMOVED WHEN NO LONGER REQUIRED FOR OPERATION. TEMPORARY JUMPER PLACEMENT SHALL NOT AFFECT AIRCRAFT MOVEMENT OR AIRPORT OFFERTIONS.
- UNCOVER SIGNS AND EDGE LIGHT FIXTURES, REMOVE TEMPORARY JUMPERS, AND VERIFY OPERATION AT THE END OF PROJECT.

ELECTRICAL GENERAL NOTES

- 1. GROUNDS RODS AND COUNTERPOISE WIRE ARE CONSIDERED INCIDENTAL TO FIXTURE AND
- 2. ELECTRICAL CONTRACTOR SHALL COORDINATE ALL DEMOLITION AND CONSTRUCTION WITH CIVIL CONTRACTOR TO REDUCE CONFLICTS THAT AFFECT CONSTRUCTION PHASING AND SCHEDULING.
- CONTRACTOR SHALL FIELD VERIFY ALL FIXTURE STATION AND OFFSETS AND CONFIRM ALL LOCATIONS ARE WITHIN SPECIFICATION TOLERANCES.


CITY OF BUCKEYE DEVELOPMENT CODE, ORDINANCES, RULES AND REGULATIONS

- 1. INTERNATIONAL BUILDING CODE, 2018 ICC EDITION
- 2. INTERNATIONAL RESIDENTIAL CODE, 2018 ICC EDITION
- 3. INTERNATIONAL PLUMBING CODE, 2018 ICC EDITION
- 5. INTERNATIONAL FUEL GAS CODE, 2018 ICC EDITION
- 6. NATIONAL ELECTRIC CODE (NEC) NFPA 70, NEC 2017 EDITION
- 7. INTERNATIONAL FIRE CODE, 2012 ICC EDITION
- 8. INTERNATIONAL EXISTING BUILDING CODE, 2012 ICC EDITION
- 9. INTERNATIONAL ENERGY CONSERVATION CODE, 2018 ICC EDITION
- 10. INTERNATIONAL PROPERTY MAINTENANCE CODE, 2012 ICC EDITION
- 11. CITY OF BUCKEYE DEVELOPMENT CODE AS ADOPTED ARTICLE ONE TO ARTICLE EIGHT AS A PART OF CHAPTER 7 OF THE BUCKEYE CITY CODE.
- 12. CITY OF BUCKEYE PUBLIC WORKS AMENDMENTS AS ADOPTED ORDINANCE 460 CHAPTER 12

 LAND DIVISION AND STANDARDS OF THE MARICOPA ASSOCIATION OF GOVERNMENT (MAG)
- 13, CITY OF BUCKEYE AMENDMENTS TO THE ABOVE REFERENCE CODES.

GENERAL NOTES FOR CONDUIT INSTALLATION


- CONCRETE ENCASED DUCTBANKS SHALL BE USED WHEN CROSSING UNDER PAVEMENTS EXPECTED TO CARRY ARCRAFT LOADS SUCH AS RUNWAYS, TAXIWAYS, TAXIH-LANES, RAMPS, AND APRONS OR VEHICULAR TRAFFIC SUCH AS SERVICE ROADS. WHEN UNDER PAVED SHOULDERS AND OTHER PAVED AREAS, CONDUIT AND DUCTBANKS SHALL BE ENCASED USING FLOWABLE FILL FOR PROTECTION.
- UNDER PAVEMENT, THE TOP OF THE DUCTBANKS SHALL NOT BE LESS THAN 18 INCHES BELOW THE SUBGRADE: IN OTHER LOCATION THE TOP OF THE DUCTBANK OR UNDERGROUND CONDUIT SHALL BE NOT LESS THAN 18 INCHES BELOW FINISHED GRADE.
- 3. DUCTBANKS SHALL BE INSTALLED SO THAT THE TOP OF THE CONCRETE ENVELOPE IN NOT LESS THAN 18 INCHES BELOW THE BOTTOM OF THE BASE OR STABILIZED BASE COURSE LAYERS WHERE INSTALLED UNDER RUNWAY, TAXIMASY, APPONS, OR OTHER PAVED AREAS, AND NOT LESS THAN 18 INCHES BELOW FINISHED GRADE WHERE INSTALLED IN UNPAVED AREAS.
- 4. ALL DUCTBANKS SHALL BE PLACED ON A LAYER OF CONCRETE NOT LESS THAN 3 INCHES THICK PRIOR TO ITS INITIAL SET. THE CONTRACTOR SHALL SPACE THE CONDUITS NOT LESS THAN 3 INCHES APART (MEASURED FROM OUTSIDE WALL TO OUTSIDE WALL.
- 5. ALL SUCH MULTIPLE CONDUITS SHALL BE PLACED USING CONDUIT SPACERS, APPLICABLE TO THE TYPE OF CONDUIT. CONCRETE SHALL BE PLACED AROUND AND ON TOP OF THE CONDUITS NOT LESS THAN 3
- 6. CONDUIT FORMING THE DUCTBANK SHALL BE INSTALLED USING CONDUIT SPACERS. #4 REINFORCING BARS SHALL BE DRIVEN VERTICALLY INTO THE SOIL A MINIMUM OF 6 ROHES TO ANCHOR THE ASSEMBLY INTO THE ASSEMBLY BIND SHALLED AT 5 FEET
- 7. ALL PAVEMENT SURFACES THAT ARE TO HAVE DUCTS INSTALLED THEREIN SHALL BE NEATLY SAW CUT TO FORM VERTICAL FACE. ALL EXCAVATION AND BACKFILL SHALL BE INCLUDED IN THE CONTRACT WITH PRICE
- 8. BARE SOLID #6 ANG COPPER COUNTERPOISE WIFE SHALL BE INSTALLED FOR LIGHTNING PROTECTION OF THE UNDERGROUND CABLES. THE COUNTERPOISE CONDUCTOR SHALL BE INSTALLED NO LESS THAN 8 INCHES MINIMUM OR 12 INCHES MAXIMUM ABOVE THE RACEMY OR CABLE TO BE PROTECTED, EXCEPT AS
 - A. THE MINIMUM COUNTERPOISE CONDUCTOR HEIGHT ABOVE THE RACEWAY OR CABLE TO BE PROTECTED SHALL BE PERMITTED TO BE ADJUSTED SUBJECT TO COORDINATION WITH AIRFIELD LIGHTING AND PAVEMENT DESIGNS.
 - B. THE COUNTERPOISE CONDUCTOR HEIGHT ABOVE THE PROTECTED RACEWAY(S) OR CABLE(S) SHALL BE CALCULATED TO ENSURE THAT THE RACEWAY OR CABLE IS WITHIN A 45-DEGREE AREA OF PROTECTION (45 DEGREES ON EACH SIDE OF VERTICAL CREATING A 90-DEGREE
- 9. INSTALL A PLASTIC, DETECTABLE, RED, 3 INCH WIDE TAPE LOCATED 8 INCHES (MINIMUM) BELOW GRADE ABOVE ALL UNDERGROUND CONDUIT OR DUCT LINES NOT INSTALLED UNDER PAYEMENT. UNDERGROUND ELECTRICAL WARNING (CAUTION) TAPE SHALL BE INSTALLED IN THE TRENCH ABOVE ALL UNDERGROUND DUCTBANKS AND CONDUIT IN UNPAYED AREAS. THE WARNING TAPE SHALL BE LOCATED 6 INCHES ABOVE THE DUCT/CONDUIT OR THE COUNTERPOISE WIRE IF PRESENT.
- 10. PROVIDE MULE TAPE IN ALL NEW (UNUSED) CONDUITS. PLUG ENDS IN HANDHOLES
- 11. P-610 CONCRETE ENCASEMENT UNDER FULL STRENGTH PAVEMENT AND P-153 CLSM ENCASEMENT UNDER PAVED SHOULDERS OR INFIELD PER SPECIFICATION L-110.
- 12. INSTALL A #6 BARE COPPER COUNTERPOISE ABOVE EACH DUCT ASSEMBLY FROM HANDHOLE TO HANDHOLE AND EXOTHERMICALLY WELD TO GROUND RODS AT EACH HANDHOLE.
- 13. INSTALL LIGHTING SERIES CIRCUITS AS FOLLOWS:
 - A. ONE CIRCUIT (1 OR 2 CONDUCTORS) PER 2"C. LIMIT 4"C TO NO MORE THAN EIGHT (8) CONDUCTORS. B. START INSTALLATION IN BOTTOM CONDUITS OF DUCT ARRY, LEAVING UPPER CONDUITS EMPTY
- 14. ALL UNDERGROUND CONDUITS SHALL MAINTAIN A 12" (MIN.) SEPARATION FROM ALL OTHER (EXISTING OR NEW) UNDERGROUND FACILITIES UNLESS NOTED OTHERWISE ON DRAWINGS
- 15. CONDUIT IN DUCTBANK(S) ARE TO BE STACKED NO MORE THAN FOUR (4) CONDUITS. IF MORE CONDUITS ARE NEEDED. THE WIDTH OF THE TRENCH IS TO BE INCREASED
- 16. WHERE PAVEMENT IS EXISTING AND REPAIR/REPLACEMENT IS REQUIRED, REPLACE IN KIND. ANTICIPATE THREE (3) INCHES OF ASPHALT ON CLSM SLURRY ENCSED DUCT SECTION. THIS SHALL BE INCIDENTAL TO THE COST OF REPROFIT DUCTEBANK INSTALLATION.
- 17. ADJUST DEPTH TO 18"-24" TOTAL FOR CONDUIT INSTALLATION BETWEEN OR INTO L-867/L-868 BASE CAN.
- 18. INSTALL ONLY ONE CIRCUIT PER CONDUIT.





BUCKEYE MUNICIPAL AIRPORT E1.2





04/22/2022 03/30/2023 1018028.05 36 of




















I	0.01	SIGN WITH	F10F 1	FACE B	5105 1	FACE B					
~~~~~	SIGN NUMBER	FACE DESIGNATION	FACE A MESSAGE	MESSAGE	FACE A COLOR	COLOR	STYLE	CLASS	SIZE	SHEET NUMBER	SCOPE OF WORK
}	SGN-1	A B <u>← D3</u> <mark>    </mark>	BLANK	← D3   H   A →	вк	BK/Y   Y/BK  BK/Y	2	2	1	E3.4	INSTALL NEW L-858(L) LED SIZE 1, 4-MODULE AIRFIELD GUIDANCE SIGN AND ISOLATION TRANSFORMER ON NEW CONCRETE BASE.
ADD ALT	SGN-2	A B 4 J DE	BLANK	← J   D3	ВК	BK/Y   Y/BK	2	2	1	E3.4	INSTALL NEW L-858(L) LED SIZE 1, 2-MODULE AIRFIELD GUIDANCE SIGN AND ISOLATION TRANSFORMER ON NEW CONCRETE BASE.
	SGN-3	A	BLANK	J   D3 →	вк	Y/8K   8K/Y	2	2	1	E3.4	INSTALL NEW L-858(L) LED SIZE 1, 3-MODULE AIRFIELD GUIDANCE SIGN AND ISOLATION TRANSFORMER ON NEW CONCRETE BASE.
BASE BID	SGN-4	А В <mark>Ј. 35 🛧</mark>	BLANK	J  35↑	вк	Y/8K   8K/Y	2	2	1	E3.2	INSTALL NEW L-858(L) LED SIZE 1, 3-MODULE AIRFIELD GUIDANCE SIGN AND ISOLATION TRANSFORMER ON NEW CONCRETE BASE.

NOTES:


1. MODULE SIZES ARE GIVEN FOR ESTIMATION ONLY AND ARE SUBJECT TO CHANGE BY SIGN MANUFACTURER

CONTRACTOR SHALL PERFORM AND SUBMIT COMPLETE FIELD SURVEY/RECORD DRAWINGS FOR ALL EQUIPMENT PRIOR TO FINAL PAYMENT. COLOR LEGEND:

BK = BLACK Y = YELLOW



AIRFIELD GUIDANCE SIGN SCHEDULE





# EDGE LIGHTING CONDUIT IN AC INFIELD PAVEMENT DETAIL

3" WIDE DETECTABLE FOIL MARKER TAPE WITH—INSCRIPTION "CAUTION ELECTRIC LINES BURIED BELOW" (BLACK LETTERS ON RED BACKGROUND) FINISHED GRADE REPLACE AND COMPACT EXCAVATED
MATERIAL TO EXISTING GRADE #6 BARE Cu COUNTERPOISE WIRE CLSM SLURRY PVC CONDUIT(S)-SIZE AND NUMBER AS REQUIRED 3" INSTALL #3 REBAR AND TIE TO CONDUIT SPACERS TO PREVENT FLOATING. DRIVE REBAR 18" MIN. INTO THE TRENCH BOTTOM

ALL DIMENSIONS ARE MINIMUM.

DETAIL APPLICABLE FOR ALL CONDUIT BETWEEN L-867/868 BASE CANS.




### 3" WIDE DETECTABLE FOIL MARKER TAPE WITH-INSCRIPTION "CAUTION ELECTRIC LINES BURIED -FINISHED GRADE BELOW" (BLACK LETTERS ON RED BACKGROUND) REPLACE AND COMPACT EXCAVATED MATERIAL TO EXISTING GRADE #6 BARE Cu COUNTERPOISE WIRE CLSM SLURRY PVC CONDUIT(S)-SIZE AND NUMBER AS REQUIRED 3" INSTALL #3 REBAR AND TIE TO CONDUIT -SPACERS TO PREVENT FLOATING, DRIVE REBAR 18" MIN. INTO THE TRENCH BOTTOM

ALL DIMENSIONS ARE MINIMUM





1. SEE SHEET E1.2 FOR CONDUIT INSTALLATION NOTES.




ALL DIMENSIONS ARE MINIMUM


CONCRETE ENCASED (CE) CONDUIT DUCTBANK


BUCKEYE MUNICIPAL AIRPORT 5.1 REPACKAGE - 03/30/2023 /2  $\sqrt{3}$ DUCTBANK DETAILS DIBBLE (CR) APPROVED MAY 12 2022 CITY OF BUCKEYE ENGINEERING AS-BUILT SEAL 04/22/2022 03/30/2023 46 of 67




1018028.05










761 COUNTERPOISE INSTALLATION DETAIL
TYP NTS


- COST OF GROUND RODS IS INCIDENTAL TO THE ASSOCIATED ITEMS REQUIRING GROUNDING UNLESS OTHERWISE SPECIFIED.
- WHERE POSSIBLE, NEW COUNTERPOISE SYSTEM SHALL BE CONNECTED TO ANY EXISTING COUNTERPOISE SYSTEM ENCOUNTERED.
- GROUNDING ELECTRODES INSTALLED AS PART OF THE COUNTERPOISE SYSTEM SHALL BE SPACED AT DISTANCES NO GREATER THAN 500 FT. (MAX).
- 4. REFER TO CONDUIT/DUCT BANK DETAILS FOR DEPTHS.





#### JUNCTION CAN GENERAL NOTES:


- LEAVE APPROXIMATELY 10 FEET (FIVE (5) FEET MIN. EACH END) OF EACH CABLE COILED IN JUNCTION CAN SO THAT EACH CABLE MAY BE RAISED A MINIMUM OF TWO (2) FEET ABOVE TOP OF CAN.
- CONTRACTOR SHALL PROVIDE CABLE CIRCUIT IDENTIFICATION (ID) MARKERS ATTACHED TO EACH CABLE ENTERING AND LEAVING JUNCTION CANS. IF NO L—823 CONNECTOR IS PRESENT, LEAVE ONE (1) FOOT OF SPACE BETWEEN ID MARKERS.
- 3. CONTRACTOR SHALL INSTALL L-823 CONNECTORS IN A CONSISTENT MANNER FROM JUNCTION CAN TO THE NEXT. EACH SEGMENT OF #8 L-824C, 5KV CABLE IN THE AIRFIELD SHALL HAVE A MALE L-823 CONNECTOR ON ONE END AND A FEMALE CONNECTOR ON THE OTHER.



# 961 PRE-CAST L-867 FIXTURE BASE/JUNCTION CAN NTS

#### NOTES:

- ONE-PIECE SONOTUBES OF CORRECT DIAMETER FOR 6" MIN.
  CONCRETE SURROUND MAY BE UTILIZED FOR ONE-TIME USE ONLY
  FOR SIZE B CANS. ROUND COLUMN FORMS SPECIFICALLY DESIGNED
  FOR MULTIPLE USE MAY BE USED.
- CONTRACTOR SHALL SUBMIT ON SPECIFIC PRE-CAST MEANS AND METHODS FOR ENGINEER REVIEW AND APPROVAL.




48 of 67



1018028.05

IS\21000\21040 - BUCKEYE TXY & APRON RECONSTRUCTION PHASE II\CAD\CAD SHEETS\21040 E5.3 - JUNCTION CAN DETAILS.DWG Mer. 30, 2023 9:55

Á




KEYED NOTES:

7. FACE INSERT PANEL
8. LAMP SOCKET
9. LAMP SOCKET
10. TERMINAL BLOCK
11. CABLE CLAMP
12. FAA L-823 PLUG
13. SLIP FILTER

14. FRANGIBLE COUPLING (6" LENGTH)
15. FLOOR FLANGE
16. BRIGHTNESS CONTROL TRANSFORMER
17. TETHER

1, WHEN JOINING TWO SIGNS FOR ONE ARRAY. PROVIDE WHEN JOINING TWO SIGNS FOR ONE ARRAY, PROVIDE NEW SCLT-6 SIZE 1 MULTIMODE INSERT (TREE) AND S7-A SIZE 1 FACE INSERT CHANNEL (TRACK) OF THE CORRECT COLOR ADDED, DO NOT PROVIDE END PLATES IN THE MIDDLE OF THE ARRAY.


PROVIDE EXTERNAL DISCONNECT SWITCH IN WEATHERPROOF ENCLOSURE, FROM MANUFACTURER.



B POWER/SUPPORT LEG

CABLE PREPARATION (NOTE 2) -THE SPLICE KIT PIN AND RECEPTACLE HOUSING THE SPLICE KII PIN AND KECEPIACLE HOUSING ENDS SHALL BE COVERED WITH AN 8" MIN. SECTION OF APPROVED HEAT-SHRINKABLE TUBING WITH INTERNAL ADHESIVE BEYOND THE PIN AND RECEPTACLE HOUSING ENDS. USE SCOTCH 33+ OVER CONNECTION XXX L-823 LINE RECEPTACLE END L-823 LOAD PLUG END XXX FOR SPLICES INSIDE HANDHOLES

NOTES



#### FOR SPLICES INSIDE CANS

PROVIDE MALE AND FEMALE L-823 CONNECTORS AS REQUIRED ON EACH CONDUCTOR IN EACH BASE, HANDHOLE, OR MANHOLE TO ALLOW ISOLATION OF HOMERUN CIRCUIT, NO STRAIGHT—THROUGH ALLOWED.

2. ALL CABLE ENDS SHALL BE PREPARED WITH THE USE OF A TAPERING TOOL SPECIFICALLY DESIGNED FOR USE WITH L-824 CABLES.

3. PLUG AND RECEPTACLE END FITTINGS SHALL BE CRIMPED ONTO THE CONDUCTOR BY USE OF AN AIRPORT PERSONNEL ACCEPTED RATCHETING TYPE CRIMPING TOOL.


4. AT THE POINT OF CONNECTION WITH THE EXISTING FIELD CIRCUITS, INSTALL NEW L-823 PLUGS ON BOTH THE NEW AND EXISTING CABLES, VERIFY INSULATION TYPES OF BOTH NEW AND EXISTING CABLES AND COORDINATE WITH TERMINATION KITS TO ASSURE PROPER AND WATERPROOF FIT.

INSTALL SCOTCH 33+ VINYL ELECTRICAL TAPE ON CONNECTION AFTER PULLING SLEEVE OVER COMPLETE KIT.

6. THERE SHALL BE NO SPLICES BETWEEN LIGHTS, ONLY IN BASES OR HANDHOLES.


7. PROVIDE AND INSTALL NON-CONDUCTIVE CIRCUIT IDENTIFICATION TAGS ATTACHED TO EACH SIDE OF ALL CONNECTOR KITS.

8. ON THE CABLES FOR THE TAXIMAY AND SIGNAGE CIRCUITS, TAPE FROM THE BACK END OF THE CONNECTOR KIT ONTO CABLE FOR 3" EACH, BLUE THEN WHITE PHASE TAPE FOR SIGNS, BLUE ONLY PHASE TAPE FOR TAXIMAY EDGE LIGHTS, FOR FASTER IDENTIFICATION AND MATCH EXISTING MANHOLE LAYOUTS.







AND 5KV SPLICE



(A)L-858(L) LED AIRFIELD GUIDANCE SIGN









901 ELEVATED EDGE LIGHT DETAIL
TYP NTS

NOTE: CONTRACTOR MAY INSTALL ADJUSTABLE OR ONE-PIECE L-867B BASE CAN IN PAVED INFIELDS. COORDINATE WITH GRADING AND PAVING OPERATIONS ACCORDINGLY.



892 L-853 TAXIWAY RETROREFLECTIVE MARKER



BUCKEYE MUNICIPAL AIRPORT SHEET ID: E5.6



~~~~	NUMBER	STATION	OFFSET	LAMP	TRANSFORMER	CIRCUIT
} [TEL-1	14+66.88	89.39' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (H)
}	₹TEL-2	14+97.89	67.08' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (H)
}	TEL-3	15+28.72	44.76' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (H)
}	TEL-4	15+66.28	38.63' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
}	TEL-5	16+03.85	32.50' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
}	} TEL−6	16+31.39	31.57' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
ADD ALT	TEL-7	16.+91.99	29.54' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
{	TEL-8	17+52.60	27.50' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
}	TEL-9	18+09.71	27.50' RT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
}	}TEL-10	18+53.39	15.84' RT	LED	10/15W	TAXIWAY (J)
}	{TEL-11	18+84.87	16.00' LT	LED	10/15W	TAXIWAY (J)
{	TEL-12	40+77.00	27.50' RT	LED	10/15W	TAXIWAY (J)
}	TEL-13	41+07.86	27.50' RT	LED	10/15W	TAXIWAY (J)
} _		41+42.34	27.50' RT	LED	10/15W	TAXIWAY (J)
}	TEL-15	43+25.73	27.50' RT	LED	10/15W	TAXIWAY (J)
}	{TEL−16	45+25.31	27.50' RT	LED	10/15W	TAXIWAY (J)
}	TEL-17	47+24.88	27.50' RT	LED	10/15W	TAXIWAY (J)
}	}TEL-18	49+24.46	27.50' RT	LED	10/15W	TAXIWAY (J)
{	TEL-19	50+11.70	27.50' RT	LED	10/15W	TAXIWAY (J)
}	}TEL-20	50+59.62	27.50' RT	LED	10/15W	TAXIWAY (J)
}	{TEL-21	51+46.86	27.50' RT	LED	10/15W	TAXIWAY (J)
}	TEL-22	51+94.52	27.50' RT	LED	10/15W	TAXIWAY (J)
}	TEL-23	52+81.76	27.50' RT	LED	10/15W	TAXIWAY (J)
}	}TEL−24	53+32.05	27.50' RT	LED	10/15W	TAXIWAY (J)
BASE BID	}TEL-25	54+26.95	27.50' RT	LED	10/15W	TAXIWAY (J)
}	{TEL-26	55+29.30	27.50' RT	LED	10/15W	TAXIWAY (J)
}	}TEL-27	55+80.59	27.50' LT	LED	10/15W	TAXIWAY (J)
}	}TEL−28	55+29.48	27.50' LT	LED	10/15W	TAXIWAY (J)
}	{TEL-29	54+78.22	27.50' LT	LED	10/15W	TAXIWAY (J)
}	TEL-30	54+26.95	27.50' LT	LED	10/15W	TAXIWAY (J)
}	}TEL-31	53+75.51	27.50' LT	LED	10/15W	TAXIWAY (J)
}	TEL-32	53+31.87	27.50' LT	LED	10/15W	TAXIWAY (J)
}	TEL-33	52+81.58	27.50' LT	LED	10/15W	TAXIWAY (J)
}	}TEL-34	52+38.01	27.50' LT	LED	10/15W	TAXIWAY (J)
} [TEL-35	51+94.52	27.50' LT	LED	10/15W	TAXIWAY (J)

TAXIWAY EDGE LIGHTS


~~~~	NUMBER	STATION	OFFSET	LAMP	TRANSFORMER	CIRCUIT
: [	TEL-36	51+46.86	27.50' LT	LED	10/15W	TAXIWAY (J)
	TEL-37	51+03.34	27.50' LT	LED	10/15W	TAXIWAY (J)
	TEL-38	50+59.62	27.50' LT	LED	10/15W	TAXIWAY (J)
	TEL-39	50+11.52	27.50' LT	LED	10/15W	TAXIWAY (J)
BASE BID	TEL-40	49+68.08	27.50' LT	LED	10/15W	TAXIWAY (J)
:	TEL-41	49+24.46	27.50' LT	LED	10/15W	TAXIWAY (J)
:	TEL-42	47+24.88	27.50' LT	LED	10/15W	TAXIWAY (J)
	TEL-43	45+25.31	27.50' LT	LED	10/15W	TAXIWAY (J)
	STEL-44	43+25.73	27.50' LT	LED	10/15W	TAXIWAY (J)
	TEL-45	41+42.16	35.93' LT	LED	10/15W	TAXIWAY (J)
	TEL-46	41+07.86	45.99' LT	LED	10/15W	TAXIWAY (J)
	TEL-47	18+13.15	56.06' LT	LED	10/15W	TAXIWAY (J)
	TEL-48	17+78.85	45.99' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
	TEL-49	17+44.55	35.93' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
	TEL-50	16+89.30	33.40' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
ADD ALT	TEL-51	16+29.30	30.64' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
	TEL-52	15+90.88	32.40' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
	TEL-53	15+52.46	34.17' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (J)
	TEL-54	15+14.05	35.93' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (H)
	TEL-55	14+79.64	46.03' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (H)
	TEL-56	14+45.23	56.12' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (H)
	TEL-57	14+34.98	90.48' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (H)
	TEL-58	14+24.54	124.83' LT	30W QUARTZ HALOGEN	30/45W	TAXIWAY (H)
u∆	, ——					

#### **GENERAL NOTES**

- EQUIPMENT NUMBERS SHOWN ARE FOR CONSTRUCTION REFERENCE ONLY.
   COORDINATE WITH AIRPORT MAINTENANCE FOR LABELING OF ALL EQUIPMENT.
- 2. CONTRACTOR TO ENSURE NEW TAXIMAY EDGE LIGHT LOCATIONS DO NOT EXCEED 10 FEET FROM EDGE OF FULL STERNGTH PAVEMENT/OUTER EDGE OF TAXIMAY EDGE MARKING AND ARE IN-LUNE WITH EXISTING EDGE LIGHTING IF APPLICABLE PEFFORM FIELD ADJUSTMENTS AS NECESSARY. CONTRACTOR SHALL CONFIRM ANY DIFFERENCES OF MEASUREMENTS/DISORCPANOLES, WHEN SURVEY OF LIGHTING LOCATIONS IS BEING PERFORMED, WITH RESIDENT PROJECT REPRESENTATIVE AND ENGINEER BEFORE LIGHT BASE IS NOTALLED.
- 3, STATION/OFFSET FOR LOCATION OF TAXIWAY LIGHTING IS FROM THE CENTER/MONUMENT LINE OF NEAREST PERPENDICULAR TAXIWAY.

#### EQUIPMENT LOCATION STANDARDS TABLE

EQUIPMENT TYPE	LOCATION STANDARD	NOTES
TAXIWAY EDGE LIGHT	2'-10'	MEASURE TO CENTER OF LIGHT FIXTURE STATION/OFFSET GIVEN IS CENTER OF LIGHT FIXTURE





- BUCKEYE TXY & APRON RECONSTRUCTION PHASE II\CAD\CAD\SHETS\21040 E6.1 EQUIPMENT DATA TABLES.DMG Mar. 30, 2023 10:01 AM

INICE-#	STATION	OLISE
RRFL-1	56+17.92	46.31' RT
RRFL-2	56+10.31	27.50' LT
RRFL-3	42+75.42	20.13' LT
RRFL-4	42+25.54	11.45' LT
RRFL-5	41+66.54	11.68' LT
RRFL-6	41+41.77	22.40' LT
RRFL-7	41+29.79	46.40' LT
RRFL-8	41+28.99	177.86' LT
RRFL-9	40+69.10	177.58' LT
RRFL-10	40+69.62	47.03' LT
RRFL-11	40+69.19	00.53' RT
RRFL-12	40+69.85	48.07' RT
RRFL-13	41+15.95	48.91' RT
RRFL-14	41+67.08	49.00' RT
RRFL-15	42+25.64	48.35' RT

#### AIRFIELD GUIDANCE SIGNS DATA TABLE

CIRCUIT	OFFSET	STATION	SGN-#	~~~~
TAXIWAY (H)	150.81' LT	14+26.89	SGN-1	
TAXIWAY (J)	44.00' LT	17+46.06	SGN-2	ADD ALT
TAXIWAY (J)	35.50' RT	41+08.00	SGN-3	
TAXIWAY (J)	35.50' LT	55+60.16	SGN-4	BASE BID
LT	35.50'	55+60.16	SGN-4	BASE BID {

#### JUNCTION CAN DATA TABLE

<i>~</i> ~~~	JC-#	STATION	OFFSET
[	JC-1	14+49.31	107.57' RT
ADD ALT	}JC−2	15+51.72	60.41' RT
{	JC-3	15+32.55	52.90' LT
	JC-4	14+13.97	166.06' LT
BASE BID	}JC-5	56+06.25	296.12' LT
www	7		•
$\triangle$			

Δ

RRFL-16 42+75.42

#### GENERAL NOTES

36.81' RT

- EQUIPMENT NUMBERS SHOWN ARE FOR CONSTRUCTION REFERENCE ONLY. COORDINATE WITH AIRPORT MAINTENANCE FOR LABELING OF ALL EQUIPMENT.
- 2. OFFSETS GIVEN FOR EACH EQUIPMENT TYPE ARE MEASURED FROM NEAREST RUNWAY/TAXIWAY CENTERLINE (ALIGNMENT).
- 3. CONTRACTOR TO ENSURE AIRFIELD GUIDANCE SIGN LOCATIONS FALL WITHIN FAA SPECIFICATIONS FROM EDGE OF FULL STRENGTH PAYEMENT/OUTER EDGE OF TAXIMAY EDGE MARKING. CONTRACTOR SHALL CONFIRM MAY DIFFERENCES OF MEASUREMENTS/SOKEPHANCIS, WHEN SURVEY OF AIRFIELD GUIDANCE SIGN AND BASE IS BEING PERFORMED, WITH ENGINEER BEFORE SIGN BASE IS INSTALLED.
- 4. CONTRACTOR TO ENSURE RETROREFLECTIVE TAXIMAY EDGE MARKERS LOCATIONS DO NOT EXCEED 10 FEET FROM EDGE OF FULL STERNOTH PAVEMENT/OUTER EDGE OF TAXIMAY EDGE MARKING. CONTRACTOR SHALL CONFIRM ANY DIFFERENCES OF MEASUREMENTS/DISCREPANCIES, WHEN SURVEY OF AIRFIELD GUIDANCE SIGN AND BASE IS BEING PERFORMED, WITH ENGINEER BEFORE SIGN BASE IS INSTALLED.

#### EQUIPMENT LOCATION STANDARDS TABLE

EQUIPMENT TYPE	LOCATION STANDARD	NOTES
SIZE 1 AIRFIELD GUIDANCE SIGNS	10' - 20'	MEASURE TO SIGN EDGE CLOSEST TO TAXIWAY EDGE/OUTER TAXIWAY EDGE MARKING
RETROREFLECTIVE TAIXWAY EDGE MARKER	2'-10'	MEASURE TO CENTER OF RETROREFLECTIVE EDGE MARKER STA/OFFSET GIVEN IS CENTER EDGE MARKER
JUNCTION CAN	N/A	STATION/OFFSET GIVEN IS CENTER OF JUNCTION CAN LID

BUCKEYE MUNICIPAL AIRPORT	E6.2
2 REPACKAGE - 03/30/2023	
ENCISIONS 2	
<u> </u>	
PLAN NAME	
EQUIPMENT DATA TAE	ILES

SHEET 2

CODE PERMITTING APPROVED APPROVED APPROVED APPROVED APPROVED APPROVED O4/12/2023 CITY OF BUCKEYE ENGINEERING  LOGGINEERING LOGGINEER	DIBBL	CA CA	Teu	et Polosades III attain 1880s, Au	E 85268
APPROVED SEAL APPROVED Od/12/2023 CITY OF BUCKEYE ENGINEERING  APPROVED ENGINEERING  APPROVED Od/12/2023 CITY OF BUCKEYE ENGINEERING  APPROVED Od/12/2023  A	CORDEDMITTING	COR ENCINEEDING		ere: (490) 50s	H3540
04/12/2023 MAY 12 2022 CITY OF BUCKEYE ENGINEERING CITY OF BUCKEYE ENGINEERING AS-BULLT SEAL  DESIGN SEA			۱		
AS-BUILT SEAL DESIGN SEAL SEAL AGENT ACCORD	APPROVED	APPROVE	:D	7	
AS-BUILT SEAL DESIGN SEAL SEAL ACCORD	04/12/2023	MAY 12 20	22	į	,
A CONTRACT LA CONT			KEYE ING	SMITTAL:	
	AS-BUILT SEAL	Segge CATHERNE ALCORN		RACKING # SU	22-0001


03/30/2023 53 of 67





04/22/2022


1018028.05


Δ











O CONSTRUCTION NOTES O


- (2) INSTALL NEW L-821 AIRFIELD LIGHTING CONTROL PANEL. RECONNECT EXISTING CCRs, NAVADS AND RADIO. PROVIDE AND CONNECT CONTROL CABLING TO NEW CCR.
- 3 INSTALL NEW 4KW CCR WITH INTEGRATED S1 CUTOUT.
- New 2/C L-824 AIRFIELD LIGHTING CABLE IN
   1/2" GRS/LFMC. CONNECT FIELD CIRCUIT
   TO 5KV WIREWAY AND USE EXISTING SPARE
   4" CONDUIT FOR ROUTING TO EXTERIOR
   AIRFIELD LIGHTING HANDHOLE.
- (9) INSTALL CONTROL CABLES FROM NEW CCR TO NEW L-821 CONTROL CABINET - 4-#12, #12 GND, 3/4"GRS.
- 18) NEW 4KW CCR INPUT POWER HOME RUN 2-#10, #10 GND, 3/4" GRS CONDUIT/LFMC (CIRCUIT A-15,17).

#### REFERENCE NOTES

- 1) EXISTING CCR'S AND S1 CUTOUTS TO REMAIN IN PLACE AND OPERATIONAL DURING CONSTRUCTION.
- 2 EXISTING L-854 RADIO TO REMAIN IN PLACE AND OPERATIONAL DURING CONSTRUCTION.
- 3 EXISTING NAVAIDS POWER AND CONTROL EQUIPMENT TO REMAIN IN PLACE AND FUNCTIONAL DURING CONSTRUCTION.
- 5) COORDINATE WITH AIRPORT FOR RELOCATION OF STORED PARTS OR TOOLS LOCATED IN AIRFIELD LIGHTING VAULT BUILDING AS REQUIRED.
- 6 EXISTING 600V AND 5KV WIREWAY TO REMAIN.
- (10) EXISTING 4KW CCR TO REMAIN.
- (13) EXISTING AIR COMPRESSOR AND AIR HOSE LINE TO REMAIN.


	Е	SUCKEYE MUNICIPAL AIRPORT	E7.5
	IS	REPACKAGE - 03/30/2023	
	REVISIONS	2	
	RE	<u></u>	
١	_	_	

AIRFIELD LIGHTING VAULT - MODIFIED ELECTRICAL EQUIPMENT ELEVATIONS






Δ Δ




PANEL: A		VOLTAGE: 120/240		MAIN CB: 200		BUS AMPS: 225		
CB TYPE: BOLT-ON		MOUNTING: SURFACE		BRACING: 22K AIC		BKR AIC: 22K AIC		
CIRCUIT DESCRIPTION	BKR	CIRCUIT	LINE 1	LINE 2	CIRCUIT	BKR	CIRCUIT DESCRIPTION	
EXHAUST FAN / LIGHTS	20/1	1						
					2	20/1	RECEPTACLES	
LIGHTING CONTROL PANEL	20/1	3						
					4	20/1	SPARE	
15KW REGULATOR (RUNWAY)	100	5						
(CCR)	7				6	20	PAPI SYSTEM	
,	2	7				- /		
					8	2		
AIRPORT BEACON	30/1	9						
					10	100	15KW REGULATOR (TAXIWAY)	
OUTSIDE TRAILER POWER	40	11				7	(CCR)	
	7				12	2	(	
	2	13			1.0	-		
					14	100	ADMIN BUILDING SUBFFED	
4KW REGULATOR (TW J)	30	15		2760		/	TOTAL DE MONTO OCUMENDO	
(CCR)	/	15		2700	16	2	+	
(CCR)	2	17	2760		10	-		
	-	- 17	2700		18	20	AWOS	
GENERATOR BATTERY CHARGER	20/1	19			10	/	AWOS	
GENERATOR BATTERT CHARGER	20/1	19			20	2		
GENERATOR JACKET HEATER	20/1	21			20	- 2		
GENERATOR JACKET HEATER	20/1	21			22	20	APRON LIGHTS	
					22	20	APRONLIGHTS	
RADIO CONTROL PANEL	20/1	23						
					24	2		
VAULT RECEPTACLES	20/1	25						
					26	20	FUTURE APRON LIGHTS	
SPARE	20/1	27				/		
					28	2		
SPARE	20/1	29						
					30			
		31						
					32			
		33						
					34			
		35						
					36			
		37						
					38			
		39						
					40			
CONNECTED KVA PER PHASE			2.8	2.8	NOTES:			
				1		ITEMIN R	ED IS NEW CIRCUIT	
CONNECTED AMPS PER PHASE			23.0	23.0	EA'		HBW CIRCUIT BREAKERS	
25% OF CONTINUOUS & LIGHTING L	OAD (KVA)		0.4	0,4	<del>                                     </del>			
25/101 CONTENOUS & LIGHTENGEDAD (KVA)		2.1						
LARGEST MOTOR (25%)			0.0	0,0				
22110221 120102 (20/0)			3.0	3.0	1			
CODE KVA PER PHASE			3.2	3.2				
CODERANTERINASE			3.2	3.2	<u> </u>			
CODE AMPS PER PHASE AT 120V			26.3	26.3				
CODE AMES FER PHASE AT 120V			20.3	20.3	1			

MODIFIED PANEL A SCHEDULE







B LOAD CALCULATIONS - EXISTING SES NTS









#### DEFINITION

A COMPREHENSIVE PLAN TO LIMIT OFF-SITE SEDIMENTATION BY CONTROLLING THE SITES POTENTIAL FOR PRODUCING AIR BORNE FUGITIVE DUST AND TRACK-OUT OF SEDIMENTS.

#### PURPOSE

EVIDITIONS
SEGMENTS WHICH ARE TRANSPORTED FROM CONSTRUCTION SITES BY
STORWARDER PRIMOFF, WIRE, ERROSON AND VERNUE TRACOGUT ARE
STORWARDER PRIMOFF, WIRE PROPERTY OF THE PROPER


THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH THE REQUIREMENTS OF THE AIR POLLUTION CONTROL PERMIT.

#### APPROPRIATE APPLICATIONS


PRIMARY SOURCES OF DUST FROM DEVELOPMENT AND CONSTRUCTION ACTIVITIES ARE.

THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH THE REQUIREMENTS OF THE AIR POLLUTION CONTROL PERMIT.

1 STABILIZED CONSTRUCTION ENTRANCE



2 STABILIZED CONSTRUCTION ENTRANCE



#### NOTES:

- NOTES:

  1. Install Sediment Wattles as slopes are constructed to grade or as directed by the Engineer. Select, Install and maintain for a significant of the Engineer select. Install and maintain for a significant of the Engineer selection and in accordance with good engineering practices. No Sediment Wattles shall be installed in urban freeway medians, nor where coble barrier systems are employed.

  2. Sediment Wattles shall be in confluxous contact with trench and sides. Do not overlay wattle ends on ton of each other. A 20° Dia. wattle may be made from 2-3 rolled excellence of them. Other has a side of the sediment with the sediment wattle may be made from 2-3 rolled excellence or straw blankets.

  3. Butt adjoining wattles dripting against each other. Dive the first end public them lightly.

  4. Repell only rillis or guilles promptly. Make field adjustments and corrections of Wattle BMP Immediately If It is causing flooding, excision, and/or affecting roadway safery in soil and rock materials that can be fipped shall be constructed, wherever possible, by the construction of out slopes 21 and steeper in soil and rock materials that can be fipped shall be constructed, wherever possible, by the construction of the stall proper shall be constructed, wherever possible, by the construction of the stall proper shall be constructed where Uniformizes are used. For seeded areas, tillings shall be performed to form minor ridges and furrows parallel to new slope contours and as specified in Section 805 of the Standard Specifications and these special provisions.


  5. Divert and direct run-on water from outside of the slopes to the spillways and/or or direct search and traffic safety, nor the designed function of roadway or bridge derinage facilities.

  9. Install and maintain Sediment Wattle BMPs to carry the stormwater of at least 2-year, 2-to-our events.

  10. The Sediment Wattle BMP's pay/old item shall include all materials sedifications.

  12. Material adjustments and corrections to ensure No sensitive biological resource

3 FILTER SOCK/WATTLE/INLET PROTECTION







1018028.05

04/22/2022 03/30/2023

62 of 67





U	1	Bld Gill	ality Test 5 S Hamil g 6, Suite bert, AZ	ton Place 114 85233	Location:	aren. Der		way and Apr uckeye Mu				Во	ring	gN	0.:		B-	02	
QT Job	No:	-	18013		Drilling C	ompany:		Wildcat D	_	-		Surfac	e Bew	ation:			1	t	_
Date S	tarted		10/9/2	018	Oriller Na	mec		Dustin M	liller			Total 0	Depth:				10	ń	
Date Fi	inishe	d	10/9/2	018	Drill Rig 1	ype:		CME-55											
.09900	By:		Abdur R	ashid	Drill Meth	od:		Hollow St	em Au	ger									
Checks	nd By:		S. Sh	ah	Bore Hold	Diameter:		7.	5"			Page:					1.0	11	_
_				Ring	Split Spoon	Shelby	Sample	Rock	Casi	ng			Grou	undv	/ate	r Da	ta		_
		Symbol		R	ssX	ST	s	RC			Symbol	Date		Time	Dep	th to er (ft)	Hole Depth (	1) 100	asing oth ()
		Xamete		2.42*	1,375*	2.80*	-		-	_	\(\frac{1}{2}\)	-	+		-	-		+	
Cut		Jength	r (O.D.)	3.00*	2.00°	3.00°	-		-	_	Ā	-	+		$\vdash$	-		+	
_		ner We	inht	140 lbs	10	30	-		$\vdash$	-	¥.	_	+		Н	$\dashv$		+	_
_		nmer F		30°						_	¥		+					$^{+}$	_
_										_	FIELD	_		_	LAE	ORA	ORY		=
Depth (ft)	Graphic Log	nacs			Material C	Description			Sample ID	Sample Type	Ring Sample (blows /6")	RQD (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Gravel (%)	Sand (%)	Fines (%)	Liquid Limit (%)	Plasticity Index
	П		2.5" ASP	HALT, 6" /	AGGREGA	TE BASE O	COURSE			T									$\overline{}$
5			medium		om of borel	ole at 10.0	J foot.												
				530		ow at FUL	3 1900L												

Quality Testing, LLC 175 S Hamilton Place Bldg 6, Suite 114 Gilbert, AZ 85233				Location:	arrie: on	_	way and Ap uckeye Mu		_		Boring No.: B-03								
OT MA	Mov	GIIL			Drilling Co	neronar.		Wildcet D	_	-		Surfac	o Elou	mtion				n	
Date St	_		10/9/2		Driller Na			Dustin M	_	i Fac.		Total D	_	manufacture.			_	) ft	
Date Fi			10/9/2		Drill Rig T			CME-55		_		TOTAL	Apper.		_	_	,,	<i>y</i> n	_
		α	Abdur R		-					_		-	_		_	_	_	_	_
Logged	÷							Stern Auger											
Checks	Checked By: S. Shah								.5"	_		Page:	_					of 1	
_	_	Symbol		Ring	Spilit Spoon SSIX	Shelby Tube ST	Bulk Sample S	Rock Core RC	Casi	19	Symbol	Date		undv	vate	r Da th to	Hole Depth		asin
In		Nameter	(ID)	2.42"	1.375"	2.80*	° M0	RU		-	∇	LABO	+	Hilling	Wab	er.(ft).	Depth	(tt) De	epth.(
			(O.D.)	3.00*	2.00*	3.00*	-				¥		+		+			+	
		Length		18"	18"	30"	-				Ā		$^{+}$		†				
Hammer Weight 140 lbs									¥										
	Har	nmer Fa	al	30"							¥		$\perp$					$\perp$	
_ 8								-	П	FIELD	_			LAE	ORA	ORY	2		
Depth (t)	Snaphic Log	1803			Material	Description			9	Sample Type	Ring Sample (blows /6")	8	Dry Unit Weight (pcf)	38	8	3	2	Jquid Limit (%)	Plasticity Index
Pd.	raphi	SS			Material	Nescription			Sample ID	old	Sas	RaD (%)	D'AB	Moisture Content (%)	Gravel (%	Sand (%)	Fines (%)	1	45
	0								8	Sa	E.S.	~	6	≥ 8	ĕ	os.	α	ig.	Piese
			2.5" ASP	HALT, 9" /	VGGREGA	TE BASE (	DOURSE			П									
SC- (SC-SM) Clayer Sity SAN																			
SC- (SC-SM) Clayey Sity SM slightly damp				ly SAND; tr	ace gravel	light brow	n, dense,												
5 -			medium																
	m		medum	aurise															
	a																		
	渊																		
10 -	1410			Both	om of borel	noie at 10.0	feet.			П									
١.																			
	Ш																		
	1																		
	H																		
	1																		
												1							


0	1	17: Bld	ality Test 5 S Hamil g 6, Suite	ing, LLC ton Place 114	Project No Location:	ame: BM	Airport Taxir	way and Ap uckeye Mu				Во	ring	g N	o.:		В	04			
Gilbert, AZ 85233 QT Job No: 18013.00 Date Started: 10/9/2018					Drilling Co	nemonary.		Wildcat D	_	÷	ort	Surface Elevation:					n				
_	_				Driller Name: Dustin Mi				_			Total Depth:					10 ft				
Date Fi			10/9/2		Drill Rig T			CME-55		-		TOSALL	Apper.	_	_	_	10 11				
_		κα			-					-		-	_	_	_	_	_	_	_		
Logged	÷		Abdur R		Drill Meth			Hollow S		ger											
Checks	d By:		S. Sh		Svilt	Diameter: Shelby	Bulk		.5"		_	Page:	_				1 of 1				
$\vdash$	-	Symbol		Ring	SSX	Tube	Sample	Rock Core RC	Casi	19	Symbol	Date		undv Time	Dep	th to	ta Hole Depth	- 10	asing		
In		Diameter	(ID)	2.42*	1.375*	2.80*	° 000	RC		-	∑ Symbol	LABO	+	THING	Wab	er.(ft)	Depth	(ft) De	opth.(ft		
		Diamete		3.00*	2.00*	3.00*	-			_	¥		+					+			
- 00		Length	(0.00)	18"	18"	30"	-			_	¥.		+					+			
		mer We	inht	140 bs	-10					_	¥		+		+			+			
		mmer F		30*						_	¥		+		+			+			
-	m					_		_			FIELD		Ė		LAE	IORA1	TORY	_			
2	8								_	2	8.		6	- 3	_		_	8	X		
Depth (ft)	Snaphic Log	1803			Material D	Description			Sample ID	Sample Type	Ring Sample (blows /6")	RQD (%)	Dry Unit Weight (pcf)	Moisture Content (%)	Bravel (%)	Sand (%)	Fines (%)	Liquid Limit (%)	Plasticity Index		
å	Snag	-							Ę	18	8 ac	ğ	68	Mob	8	ă	8	Pg F	100		
	1								95	S	20		2	-0	٥			ŝ	5		
			2.5" ASP	HALT, 5" A	VOGREGA	TE BASE (	COURSE														
	-83	sc	(SC) Clay	yey SAND:	trace graw	si, light bro	wn, loose t	o medium													
	188		Gerise, si	gany com	,																
	100																				
	88																				
	100																				
	W																				
	188																				
5 -	100																				
	188																				
	182																				
	100																				
	w																				
	188		medium	dense																	
	182																				
	882																				
	188																				
10 -	100									L		_	_		_	_		_	_		
				Both	om of borel	nole at 10.0	feet.														
	-																				
	1																				
-	1																				
l																					
	1																				
1													ı								


0	1		ality Test 5 S Hamil g 6, Suite bert, AZ		Project N Location:	me: BM		way and Ap uckeye Mu				Во	ring	g N	o.:		B-	05	
QT Job	. Mari	- Gill	18013		Drilling C			Wildcat D	_	-	uri	Surfac			_	_	-		_
Date S			10/9/2		Driller Na			Dustin M	-	-		Total D		aucut.			10		_
Date F			10/9/2		Drill Rig 1			CME-55		_		TOTAL	Alpen.				10	-	_
Logged			Abdur R		Drill Meth			Hollow St	om for	~~			_	_	_	_	_	_	-
Checks	_	_	S. Sh		-	Diameter		Picecew or		gur		Page	_	_	_	_		_	_
Cheoxi	ва ву:		8. Sh	Ring	Solit	Shelby Tube	Bulk Sample	Rock Core	Cesi		_			undv		- D-	1 0	( 1	
_	,	lodmy		R	SSX	ST	Sample	RC	Cum		Symbol	Dete		Time	Dep	th to	Hole Depth (		asin
In		lamete	(LD.)	2.42*	1,375"	2.80*	-				¥	-		-	11/20	×.(10)	Liepan.c	mire	gen.i
Out	tside C	Namete	r (O.D.)	3.00*	2.00*	3.00*	-				¥							Т	_
	ı	.ength		18"	18°	30°	-				¥							Т	
		ner We		140 lbs							¥.								
	Har	nmer F	ali	30"					-	_	₽		Д.			IORAT	no mur	_	_
Depth (t)	Graphic Log	nacs			Material C	Nescription			Sample ID	Sample Type	Ring Sample (blows /6")	RQD (%)	Dry Unit Weight (pof)	Moisture Content (%)	Gravel (%)	Sand (%)	Fines (%)	Liquid Limit (%)	Plantfelly Inday
_			2.5" ASP	HALT, 4°	AGGREGA	TE BASE	COURSE			Г			П						П
5																			
	-			Both	om of borel	iole at 10.i	) feet.												


E	BUCKEYE MUNICI	PAL AIRPORT	SHEET	1.02
s	A REPACKAGE	- 03/30/2023		
SEVISIONS	2			
æ	<u>3</u>			
PL	AN NAME			
		OTECHNICAL ORING LOGS		
EN	GINEER INFORMATION	DIBBI	7	
		DIBBL		
CC AF	IB PERMITTING PROVED SEAL	COB ENGINEERING APPROVED SEAL		
	APPROVED	APPROVED		<u>fa</u>



COS PERMITING APPROVED 04/12/2023 CITY OF BUCKEYE ENGINEERING	APPROVED SEAL  APPROVED  MAY 12 2022  CITY OF BUCKEYE  ENGINEERING	IBMITTAL:	2nd Submittal		0005-026-20
AS-BUILT SEAL	FOR INFORMATION ONLY	TRACKING # SU		2.0001	P.NO. 3-04-
ORIGINAL PLAN DATE 04/22/2022 PROJECT NUMBER 1018028.05	03/30/2023 SHEET NUMBER 64 of 67	COB PLAN TRAC		COB PERMIT # ENGCIP-2	EAA AI







2nd Submittal

ENGCIP-22-0001

Airport Taxiway & S. Apron Reconstruction Ph2

Final CSPP

2R - FOR REVIEW

RECEIVED

04/04/2023

CITY OF BUCKEYE by: NV ENGINEERING

# FINAL CONSTRUCTION SAFETY & PHASING PLAN

Buckeye Municipal Airport
Taxiway & South Apron
Reconstruction
Phase II

FAA AIP No.: 3-04-0005-026-2023 Dibble Project No.: 1018028.05

Prepared For: City of Buckeye

March 30, 2023





## **No Further Comments**

# FINAL CONSTRUCTION SAFETY & PHASING PLAN

Buckeye Municipal Airport
Taxiway & South Apron Reconstruction
Phase II

FAA AIP No.: 3-04-0005-026-2023 Dibble Project No.: 1018028.05

Prepared For: City of Buckeye 530 E. Monroe Ave. Buckeye, AZ 85326

March 30, 2023

Duane Dana, PE Project Manager

**Dibble** 

# **No Further Comments**



# Table of Contents

1.	COC	PRDINATION	
	1.1	General Project Information	3
	1.2	Contractor Progress Meetings	4
	1.3	Scope or Schedule Changes	4
	1.4	FAA/ATO Coordination	4
2.	PHA	SING	
	2.1	Phase Elements	
	2.2	Construction Safety Drawings	4
3.		AS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY	
	3.1	Affected Areas on the Airfield	
	3.2	Mitigation of Effects	6
4.	PRO	TECTION OF NAVIGATION AIDS (NAVAIDS)	•
	4.1	NAVAID Critical Areas	
	4.2	Effects of Construction on NAVAID Performance	,
	4.3	Protections of NAVAID Facilities	
	4.4	Required Distance from NAVAIDs to Construction Areas	7
	4.5	Coordination Procedures with FAA/ATO	8
5.	CON	TRACTOR ACCESS	
	5.1	Location of Stockpiled Construction Materials	
	5.2	Vehicle & Pedestrian Operations	8
	5.3	Two-Way Radio Communications Procedures	
	5.4	Airport Security	9
6.	WIL	DLIFE MANAGEMENT	10
	6.1	Trash	10
	6.2	Standing Water	10
	6.3	Tall Grass & Weeds	10
	6.4	Poorly Maintained Fencing and Gates	10
	6.5	Disruption of Existing Wildlife Habitat	10
	6.6	Airport Wildlife Management Procedures	10
7.	FOR	EIGN OBJECT DEBRIS (FOD) MANAGEMENT	10
8.	HAZ	ARDOUS MATERIAL MANAGEMENT	11
9.	NOT	TFICATIONS OF CONSTRUCTION ACTIVITIES	11
	9.1	Points of Contact	11
	9.2	Local ATO/Technical Operations Personnel	11
	9.3	ATCT Managers on Duty	11
	9.4	Authorized Representatives to the FAA's Operational Control Center (OCC)	
	9.5	OCC Notification About Closed and/or Hazardous Conditions on the Airfield	
	9.6	Notice to Airmen (NOTAM)	
	9.7	Emergency Notification Procedures	
	9.8	Coordination with ARFF for Non-Emergency Issues	
	9.9	Notification to the FAA and Airport Users	
	-	<b>A</b>	

# **No Further Comments**



		FAA Notification Under CFR Parts 77 and 157	
	9.11	FAA Reimbursable Agreements	12
	9.12	Affected Instrument Approach Procedures	12
10.	INSP	ECTION REQUIREMENTS	13
	10.1	Daily (or more frequent) Inspections	13
	10.2	Final Inspections	13
	10.3	Inspection Checklist	13
11.	UND	ERGROUND UTILITIES	13
12.	PENA	ALTIES	14
13.	SPEC	TAL CONDITIONS	14
14.	RUN	WAY & TAXIWAY VISUAL AIDS	14
		General	-
		Markings	-
		Lighting and Visual Aids	
		Signs	
15.	MAR	KING & SIGNS FOR ACCESS ROUTES	15
16.		ARD MARKING & LIGHTING	
	16.1	General	15
	16.2	Barricades	16
17.	WOR	K ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION	17
18.	PRO	TECTION OF RSA'S, TSA'S, OFA'S, OFZ'S, AND APPROACH/DEPARTURE SURFACES	17
		Runway Safety Area (RSA)	
	18.2	Runway Object Free Area (ROFA)	,
	18.3	Obstacle Free Zone (OFZ)	,
		Taxiway Safety Area (TSA)	
	_	Taxiway Object Free Area (TOFA)	
	18.6	Runway Approach & Departure Surfaces	18
19.	OTH	ER LIMITATIONS ON CONSTRUCTION	
	19.1	Prohibitions	
	19.2	Restrictions	18
		Appendices	
App	endix	A Construction Phasing Plans	
App	endix	B Inspection Checklist	В



## 1. COORDINATION

## 1.1 General Project Information

This project will reconstruct and realign the southern taxiways consisting of approximately 12,000 square yards (SY) of asphalt concrete (AC) pavement. New LED taxiway edge lighting and airfield guidance signage will be installed, along with new underground conduit infrastructure and upgrades in the Electrical Vault including providing a new Constant Current Regulator (CCR). A new storm drain will serve the infield areas between Taxiway 'J' and the airport hangars and will outlet into a channel running parallel to Taxiway 'J'. A new culvert will convey flows underneath Taxiway 'D3' from the infield area to the south.

This Construction Safety and Phasing Plan (CSPP) provides specific information to the Contractor and/or Subcontractors contracted to carry out the construction contract for this project. This plan includes the requirements and procedures for accident prevention, safety requirements, and security considerations at BXK. The Airport's safety objective is to achieve accident-free construction projects. Furthermore, the Contractor must be in full compliance with FAA Advisory Circular (AC) 150/5370-2G: Operational Safety on Airports During Construction. The CSPP and project safety and phasing requirements will be discussed in detail at the Pre-Bid and Pre-Construction Conferences. The Contractor is required to submit a Safety Plan Compliance Document (SPCD) to BXK describing how the contractor will comply with the requirements set forth in the CSPP.

The Contractor or Subcontractor shall conduct their operations in a manner that will provide safe working conditions for all employees, the protection of the public and all others who may be affected by construction activities. Nothing contained in this plan is intended to relieve the Contractor, Subcontractor or suppliers of the obligations assumed by the Contractor under contract with the Airport or as required by law. The Contractor shall be required to submit a SPCD to the airport describing how the contractor will comply with the requirements set forth in the CSPP.

Safety must be an integral part of the job. Full participation, cooperation, and support are necessary to ensure the safety and health of all persons and property involved in the project. The purpose of phasing, marking, barricading, and lighting of airside construction areas is to delineate hazardous areas and prevent unauthorized incursions into the areas by personnel, vehicles, equipment, and aircraft during construction; and to positively separate construction activity from aircraft operations.

A Pre-Bid Conference will be scheduled during the bidding process to allow prospective bidders an opportunity to understand the safety aspects of this project. A key topic of this meeting will include a detailed review of this CSPP, with emphasis on Contractor responsibilities for safety, as well as access and work areas in each phase.

A Pre-Construction Conference will be scheduled prior to the issuance of the Notice to Proceed. Invitees and attendees will include City and Airport staff; the Engineer-of-Record; the Resident Engineer; the Contractor's Project Manager/Superintendent; and representatives from the FAA and ADOT (in person or by phone). Relevant safety-related issues will be discussed in detail at this meeting.

Topics of discussion will include the FAA Advisory Circular (AC) 150/5370-2G: Operational Safety on Airports During Construction; project scope; the Resident Engineer's responsibility; identifying the Contractor's Superintendent; NOTAM responsibility; phasing and scheduling of work; Notice to Proceed date; safety during construction; security, badging and escorting requirements; quality control and testing; test reports; maintenance of record drawings; and other contract and Federal requirements.

The Contractor is required to submit an overall project schedule at the Pre-Construction Conference which will allow Airport staff, the Engineer and the Contractor to identify affected areas during construction.



## 1.2 Contractor Progress Meetings

Weekly construction progress meetings will be held where the invitees and attendees will include at minimum the Airport staff, the Resident Engineer, the Contractor's Project Superintendent, and the lead personnel of each Subcontractor. In addition to the discussions on the progress of the project, operational safety procedures identified within the SPCD will be reviewed and discussed.

## 1.3 Scope or Schedule Changes

The Contractor will be required to immediately notify the Resident Engineer and Airport Staff of any changes to the original project scope or schedule. The Airport will coordinate (as needed) any changes with the impacted stakeholders, (i.e. tenants, FAA, etc.).

## 1.4 FAA/ATO Coordination

The Airport will be responsible for coordinating as required with the FAA/ATO during construction.

## 2. PHASING

This project is divided into a Base Bid and one Additive Alternate. The Base Bid will comprise the reconstruction of approximately 1,300 feet of Taxiway 'J' with a 100-foot transition into the existing taxiway before it reaches the turn to the existing connector taxiway. If the Additive Alternate is awarded, the transition section will not be constructed, and the remainder of Taxiway 'J' through the entirety of Taxiway 'D3' will be constructed.

The project will be constructed in three phases, as displayed in **Appendix A** – *Construction Phasing Plans*.

Due to the time it could take to acquire the CCR, a long-lead item, the Contractor will be required to provide the relevant submittal to the Engineer at the Pre-Construction Conference and on its approval begin its acquisition before a formal NTP to begin construction is provided to the Contractor.

#### 2.1 Phase Elements

**Base Bid Phase 1A.** This will include pavement reconstruction of Taxiway 'J' from the intersection of the South Apron approximately 1,300 feet to the south.

- The construction duration shall be 35 Calendar Days.
- Aircraft detour routes to/from the South Apron and the Runway 35 end include using Taxiway 'A', Taxiway 'H', and Taxiway 'C'.
- Low-profile barricades will be placed around this work area and across the existing taxiway near the Taxiway 'H' intersection just outside the OFA for Taxiway 'H'. Aircraft will not have access to Taxiway 'J' nor the connector during this phase.

**Base Bid Phase 1B.** This will include the 100-foot transition from the end of Phase 1A back into the existing taxiway.

Phase 1B shall be concurrent with Phase 1A and will follow the same detouring. Phase 1B shall not
take place if the Additive Alternate is awarded. The combined construction duration of Phases 1A
and 1B shall be 35 Calendar Days.



**Phase 2A.** This will include installation of new power through existing conduit for the Taxiway 'J' lighting circuit under the South Apron to connect into the Airport Electrical Vault, and upgrades to the infrastructure inside the Airport Electrical Vault.

- Phase 2A shall begin construction 25 calendar days after the beginning of Phase 1A and shall be constructed concurrently with Phase 1A. The construction duration shall be **10 Calendar Days**.
- Low-profile barricades will be placed across the Taxiway 'C' intersection just outside the OFA for Taxiway 'H' while work is taking place in the immediate vicinity. Aircraft will be able to access the apron via Taxiway 'J' during this phase.

**Phase 2B**. This will include installation of new conduit and power for the Taxiway 'J' lighting circuit around the South Apron to connect into an existing structure south of Taxiway 'C'.

• Phase 2B shall be constructed after Phase 2A and shall not be concurrent with Phase 1A. The construction duration shall be **2 Calendar Days**.

**Phase 3.** This will include the remaining construction of Taxiway 'J' from where Phase 1A ends and includes Taxiway 'D3'.

- Phase 3 may be concurrent with Phase 1A. Phase 3 shall not take place if the Additive Alternate is not awarded. The construction duration shall be **20 Calendar Days**. The combined construction duration of Phases 1A and 3 shall be **55 Calendar Days**.
- Aircraft detour routes to/from the South Apron and the Runway 35 end include using Taxiway 'C' Taxiway 'H', and Taxiway 'B'. Back-taxiing will be required on Runway '17-35' from Taxiway 'B' to the Runway 35 end, where aircraft may use the adjoining portion of Taxiway 'A' for turning around. As such, a temporary taxiway closure marker will not be used on Taxiway 'A' to denote its closure as it would conflict with aircraft turnaround movements.
- Low-profile barricades will be placed across Taxiway 'A' at the Runway Holding Position Marking, across Taxiway 'H' just south of the Taxiway 'B' intersection, and across Taxiway 'J' south of the T-Hangars and connecting taxilanes.

**Substantial Completion – 57 Calendar Days.** This will mark the completion of all construction in phases 1, 2 and 3. A pre-final walk-though will be completed by the Resident Engineer, Airport Staff and the Contractor. The Contractor shall be provided with a Substantial Completion letter including a punchlist of any remaining items to complete before Final Completion. The construction warranty will begin from this date.

**Final Completion – 30 Calendar Days.** This will include the completion of all punchlist items noted on the Substantial Completion letter, the application of permanent pavement markings, final clean-up and demobilization.

## 2.2 Construction Safety Drawings

The Contractor is required to provide his own detailed Barricade Plans in accordance with his anticipated operations for the review and approval of the Airport.



# 3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY

#### 3.1 Affected Areas on the Airfield

#### 3.1.1 Closed or Partially Closed Facilities

No facilities (buildings or businesses) are anticipated to be closed or partially closed for the duration of this project. For runway and taxiway closures, reference **Section 2.1** *Phase Elements*.

#### 3.1.2 ARFF Access Routes

No ARFF facilities are located at BXK. Emergency vehicles will have access via the Airport Entrance Road and through the gate at the west end of the Entrance Road.

## 3.1.3 Airport Support Vehicle Access Routes

Airport support vehicle access and routes are not anticipated to be impacted by this project and will be accommodated via existing taxiway structural pavement or infield areas adjacent to the project areas.

## 3.1.4 Utilities for Firefighting

No underground utilities used for firefighting (including water) within the AOA are anticipated to be impacted by the construction of this project. While every effort has been made to include the locations and depths of known utilities within the project area, the Contractor will be required to pothole for utilities to avoid damage to them. Fire hydrants are located off-site.

## 3.1.5 Affected Approach and Departure Surfaces

The Contractor will be required to abide by the Part 77 airspace requirements at all times, including all equipment, material and batch plants that may be required for this project. Construction equipment will be limited to stay below the approach surfaces at all times. Equipment along the haul route having a height of 15-ft will be submitted to OE/AAA to be evaluated for Airspace impact.

Construction activity shall be prohibited when equipment penetrates the imaginary surface described in Title 14 CFR Part 77 and any restricted area as defined in the current edition of FAA AC 150/5300-13A, *Airport Design*, unless a favorable airspace finding has been made by the FAA and the Airport and approved by Airport Operations. Equipment that penetrates the Part 77 imaginary surface must display a red obstruction light during nighttime use and an orange and white checkered flag during the day.

3.1.6 Affected Instrument Approach Procedures and NAVAID Critical Areas No Instrument Approach Procedure or NAVAID Critical Area will be impacted by the project.

## 3.2 Mitigation of Effects

#### 3.2.1 Construction Staging Area and Haul Routes

The Contractor's staging and storage area, haul routes, and construction access areas are shown Construction Plan Sheets **GG2.01**, **GG2.02**, and **GG2.03**. The Contractor's staging area is located outside of all Object Free Areas. Construction access areas and haul routes have been established to minimize impact to airfield operations. The Contractor will be required to supply gate guards at all construction entrances to the airfield when in use. Gate guards will not be required if the gates are closed and locked.



Transient haul truck drivers are required to check in with the Contractor's security guard. The driver shall be issued an orange/white checkered flag to be mounted on the highest point of the truck; and shall be returned to the security guard upon check out. The driver shall be advised to remain on the marked haul route and follow the appropriate signs to the intended work area. At no time shall any driver be allowed to deviate from the marked haul route. Additionally, during times of low visibility or darkness, the drivers shall be required to use a flashing amber beacon.

#### 3.2.2 Temporary Taxi Operations

Temporary taxi operations and alternate routes to accommodate aircraft movement needs are discussed for each project phase in **Section 2** *Phasing*.

## 3.2.3 Detours for ARFF and Other Airport Vehicles

No ARFF facilities are located at BXK. Emergency vehicle and airport vehicle access and routes will be accommodated via existing taxiway structural pavement or infield areas adjacent to the project area and are not anticipated to be impacted by this project.

#### 3.2.4 Maintenance of Essential Utilities

Essential utilities are not anticipated to be impacted in this project. The Contractor will be required to provide temporary means to any impacted utilities until the impacted utilities are restored. Work within the electrical vault will take place during daytime shutdowns of the vault so that all airport lighting can be operable at the end of each shift.

#### 3.2.5 Temporary ATC Procedures

BXK is a non-towered airport. The Airport will be kept apprised of all construction activities throughout the duration of the project. The Contractor will provide construction schedules at least two weeks ahead of the proposed construction activities to be given to Airport staff. The Airport will be expected to provide feedback about any concerns that the Airport has for construction areas and Contractor movements. Project sketches will be provided to the Airport so that they are aware of the impacts to aircraft operations. The Airport will be responsible for issuing NOTAMs related to construction activities and restrictions.

## 4. PROTECTION OF NAVIGATION AIDS (NAVAIDS)

#### 4.1 NAVAID Critical Areas

No NAVAID critical areas will be impacted by this project.

#### 4.2 Effects of Construction on NAVAID Performance

NAVAID performance is not anticipated to be impacted by this project.

#### 4.3 Protections of NAVAID Facilities

All NAVAID's and visual aids will remain protected and in place.

#### 4.4 Required Distance from NAVAIDs to Construction Areas

NAVAID's and visual aids not impacted directly by this project are at a safe distance away from any construction activities. The contractor is anticipated to be on the opposite side of the runway from the Runway 35 PAPI. At no time should the contractor be within the vicinity of any NAVAID or visual aid.



## 4.5 Coordination Procedures with FAA/ATO

The Airport staff will be responsible for continually coordinating as required with the FAA/ATO during construction.

#### 5. CONTRACTOR ACCESS

## **5.1** Location of Stockpiled Construction Materials

All contractor materials, equipment and supplies shall be within the Contractor's designated staging and storage area. All storage areas shall be marked; debris boxes covered and area kept neat and clean of debris.

For equipment that must remain in the work area, the following conditions must be met:

- Be located outside of the runway/taxiway safety and object free areas.
- Be marked with lighted barricades around the equipment perimeter with a spacing of no more than 10-ft.
- Be coordinated at least 48 hours in advance with the Resident Engineer.
- The highest point of the equipment marked and lit with a red flashing/steady burning omnidirectional obstruction light.

Stockpiled materials are allowed only within the Contractor's designated staging and storage area:

- Remove daily all stockpiled material from within aircraft movement areas, unless otherwise directed by the Resident Engineer.
- No excavated or stored materials may remain within active runway or taxiway safety areas and object free zones.
- Stockpiled material may be located within the Air Operations Area only upon prior coordination and approval of the Resident Engineer.

## **5.2** Vehicle & Pedestrian Operations

#### 5.2.1 Construction Site Parking

Construction parking will be allowed in the Contractor's Staging and Storage Area, which is outside of any Object Free Areas. No personal vehicles will be allowed onto the airfield with the exception of inside the Contractor's Staging and Storage Area.

## 5.2.2 Construction Equipment Parking

Construction equipment parking will be in the Contractor's Staging and Storage Area for any equipment that is not in use.

#### 5.2.3 Access and Haul Roads

Access and haul roads on Airport property will be delineated with the use of low-profile barricades, flagging, flagmen, signage, escorts, or a combination thereof as shown in this CSPP and in the Plans. Contractor access and haul roads can be seen on Sheet **GG2.01**. See **Section 5.1.1** *Contractor Access Areas* for further information.



#### 5.2.4 Marking and Lighting of Construction Vehicles

All Contractor and Subcontractor vehicles must be properly marked with the company name at least four (4) inches in height on both sides of the vehicle. All vehicles must have a 3' x 3' orange and white checkered flag at the tallest point on the vehicle for daytime construction activities, and a flashing amber or yellow beacon, mounted at the highest point for nighttime construction.

All vehicle marking and lighting must comply with the most recent version of Advisory Circular 150/5210-5D, *Painting, Marking and Lighting of Vehicles Used on an Airport*.

#### 5.2.5 Construction Vehicle Operations Within AOA

For the purposes of this project, the AOA is defined as any area within the secured (fenced) area of the Airport. No vehicle shall operate within the Air Operations Area (AOA):

- In a careless or negligent manner.
- With disregard of the rights and safety of others.
- At a speed (15 MPH maximum) or in a way which endangers persons or property.
- While the driver is under the influence of drugs or alcohol.
- If such vehicle is loaded or maintained as to endanger persons or property.
- Without constant observance for operating aircraft.

## 5.3 Two-Way Radio Communications Procedures

The Contractor will be required to maintain and/or operate two-way radios. The radio frequency used at BXK is 122.975. These procedures will also be discussed at length during the Pre-Construction Meeting for this project.

## **5.4** Airport Security

Any time access is required within the Airport Operations Areas (AOA) the Contractor shall be responsible for assuring that no breaches of airport security occur. The AOA is fenced and must remain fenced at all times. The gates will remain closed and locked or a guard (with an airport issued access card) will be provided at the Contractor's expense. The Contractor will furnish gate guards with rosters of his personnel and ensure that each individual has adequate identification. The duplicate keys for each lock will be turned over to Airport authorities. The following additional measures must also be taken:

- No person shall enter the Contractor's worksite without authorization. Any person found within
  the worksite without proper identification as describe herein shall be considered unauthorized and
  shall be removed from the worksite.
- Persons authorized to provide escorts include Airport staff and designated contractor supervisors.
   Failure to provide an escort can result in loss of escort privileges, fines, revocation of the access card, or all three.
- Contractor Superintendents and Supervisors will be required to wear identifiable equipment or clothing to be easily recognized and located on site.

Reference **Section 3.2.1** Construction Staging Area and Haul Routes for additional requirements imposed on the Contractor regarding the Staging Area and Haul Routes.



## 6. WILDLIFE MANAGEMENT

## 6.1 Trash

The Contractor shall perform daily inspections of the work areas (including the Contractor's staging area) to remove any trash, debris and food scraps and place these items in an appropriate trash receptacle. Trash receptacles, regardless of type and size, must always be covered and secured to eliminate the possibility of contents from escaping.

## 6.2 Standing Water

The Contractor shall conduct his/her operations to minimize the potential for standing water. When water begins to stand on site, the Contractor shall begin pumping water to drain the area within 24 hours to prevent the attraction of wildlife.

#### 6.3 Tall Grass & Weeds

The Contractor shall mow areas under his/her responsibility including, but not limited to, project site staging and storage areas and exclusive use haul roads to prevent the growth of vegetation over 6-inches.

## 6.4 Poorly Maintained Fencing and Gates

The Contractor shall close and lock any airfield access gates that are not in use. Any fencing installed by the Contractor shall be maintained to prevent the intrusion of wildlife.

## **6.5** Disruption of Existing Wildlife Habitat

The Contractor shall report any significant wildlife sightings within the AOA to the nearest Airport employee.

## 6.6 Airport Wildlife Management Procedures

The Contractor will be required to follow any Airport Wildlife Management Procedures that are in place at the airport; however, at a minimum the Contractor will be required to perform the following:

- Close and lock any airfield access gates that are not in use.
- Report any significant wildlife sightings within the AOA to the nearest Airport employee.

## 7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

This project will include the movement of construction vehicles adjacent to active airfield pavements, therefore the Contractor will be required to maintain a fully operational sweeper vehicle on-site during the project. Furthermore, once any portion of any construction is ready to be opened to aircraft traffic, the Contractor, Resident Engineer, and Airport personnel shall walk the area to determine that all FOD that may have been generated is no longer present.

The Contractor will be required to keep water on construction areas to minimize the possibility of FOD generated by wind. The Contractor will be required to conduct FOD checks at the end of each working shift/day to remove any FOD that has made its way onto the airfield pavements from the Contractor's construction activities. Airport Operations and Construction Administration personnel will be present for these FOD checks to ensure compliance.



## 8. HAZARDOUS MATERIAL MANAGEMENT

Any hazardous or regulated waste material produced by the Contractor's operations shall be properly disposed of at the Contractor's expense pursuant to all local, state, and federal regulations. The Contractor may be required to provide test results to confirm that a contaminated area has been properly remediated.

Any hazardous materials situation that poses a threat to safety or property shall be immediately reported to emergency personnel by dialing '911' and to the nearest Airport employee.

## 9. NOTIFICATIONS OF CONSTRUCTION ACTIVITIES

#### 9.1 Points of Contact

A full list of Points of Contact and Contact Procedures will be developed prior to the Pre-Construction Meeting for this project. Under normal circumstances, all communications concerning the construction project between airport stakeholders and the contractor shall be channeled through the Resident Engineer who shall be the primary point of contact for all communications concerning the construction project. Matters relating to Airport operations will be handled through the Airport, with assistance from the Resident Engineer and/or Contractor as needed.

Contact	Phone Number	Availability
TBD Resident Engineer, Dibble		Construction Hours
Duane Dana, P.E. Engineer-of-Record, Dibble	480-365-9056	Mon-Fri, 8:00am to 5:00pm
Jeff Webbe BXK Airport Operations	623-695-4555	Mon-Fri, 8:00am to 5:00pm

## 9.2 Local ATO/Technical Operations Personnel

The Airport will be responsible for all communications with the local ATO/Technical Operations.

## 9.3 ATCT Managers on Duty

BXK is a non-towered airport.

# 9.4 Authorized Representatives to the FAA's Operational Control Center (OCC)

The Airport will develop a list of authorized representatives to the OCC prior to construction commencing. This list will be provided to the OCC by the date of the Pre-Construction Meeting.

# 9.5 OCC Notification About Closed and/or Hazardous Conditions on the Airfield

The Airport staff will be responsible for notifying the OCC about closed facilities and/or hazardous conditions at the Airport. The OCC will be notified about closed facilities as soon as practicable following reliable scheduling meetings. Unanticipated hazardous conditions will be immediately relayed to the OCC by Airport staff.



## 9.6 Notice to Airmen (NOTAM)

Construction NOTAM's will be filed by the Airport staff approximately three (3) days prior to construction beginning in the area which the NOTAM references, or prior to any change in airfield conditions which may affect operations or safety. The Contractor will be required to submit pertinent information to the airport for any construction items that would require the issuance of a NOTAM a minimum of 2 weeks prior to the work being performed.

## 9.7 Emergency Notification Procedures

For any medical and law enforcement emergencies call '911' and communicate the emergency to the Airport immediately.

The Contractor shall submit to the Resident Engineer a list of personnel who can be contacted 24 hours a day, seven (7) days a week and can respond in a reasonable time frame regarding any possible emergency on the work site. The list must include names, job title and phone numbers.

## 9.8 Coordination with ARFF for Non-Emergency Issues

BXK does not have an ARFF facility. The Contractor shall contact the Airport Manager concerning non-emergency issues of the following:

- The deactivation and subsequent reactivation of water lines and fire hydrant.
- The establishment, re-routing, or blocking of emergency routes.
- The use of hazardous materials on the airfield.

## 9.9 Notification to the FAA and Airport Users

All proposed construction activities that affect operations at the Airport will be immediately relayed to all Airport Users and the FAA by way of meetings, advisories, NOTAM's, and the filing of Form 7460 as appropriate (minimum of 60 days prior to the proposed construction) all issued by one of the Airport's designated staff or Resident Engineer.

Anticipated night work by the Contractor will need the Airport approval prior to proceeding with the night work.

#### 9.10 FAA Notification Under CFR Parts 77 and 157

No relocations of NAVAIDS are required for this project; therefore, no coordination with the FAA or notifications are required.

## 9.11 FAA Reimbursable Agreements

A FAA Reimbursable Agreement is not a method of funding for this project.

## **9.12 Affected Instrument Approach Procedures**

No Instrument approach procedure is affected by this project.



## 10. INSPECTION REQUIREMENTS

## 10.1 Daily (or more frequent) Inspections

Daily inspections will be required for areas requiring haul routes on active airfield pavements to ensure that FOD is minimized. In addition, daily inspections of Contractor access areas will be performed to help ensure safety on the airfield. Daily inspections will be conducted by an Airport Operations employee, a Contractor representative, and the Resident Engineer.

Special inspections will be required for airfield pavements that are ready to be re-opened to aircraft traffic after completion of the project. Special inspections will also be attended by an Airport Operations employee, a Contractor representative, and the Resident Engineer.

All discrepancies noted in the inspection must be corrected to the satisfaction of the Resident Engineer prior to the Contractor leaving the worksite.

Should any inspection reveal any FOD concerns, the Contractor shall have a crew ready to remove any FOD prior to reopening the pavements. Should any inspection reveal work that does not meet Contract requirements or that is deficient in any way, the Contractor shall mobilize a crew as soon as possible to remedy the deficient areas to avoid prolonging the continued closure of the areas.

## 10.2 Final Inspections

Inspections will be required at the Substantial Completion and Final Completion phase of the project. These inspections will be attended by the Contractor, Airport Manager, FAA, ADOT Aeronautics, the Resident Engineer, and Construction Administration representatives. A punch list will be developed at the Substantial Completion inspection, and any items placed on the punch list will be required to be completed within 30 days. Final Inspection will be scheduled 30 days after the substantial completion walkthrough.

Should any inspection reveal any FOD concerns, the Contractor shall have a crew ready to remove any FOD prior to reopening the pavements. Should any inspection reveal work that does not meet Contract requirements or that is deficient in any way, the Contractor shall mobilize a crew as soon as possible to remedy the deficient areas to avoid prolonging the continued closure of the areas.

## 10.3 Inspection Checklist

The Airport Manager, Operations Manager, the Engineer/Construction Manager/Resident Engineer, and the Contractor will utilize **Appendix B** – *Inspection Checklist* for evaluating the Contractor's adherence to the contract documents and this CSPP, as well as for reopening any areas to aircraft traffic.

#### 11. UNDERGROUND UTILITIES

Prior to beginning construction on the airfield, the Contractor will be required to Blue Stake and pothole (if necessary) existing utilities in the project areas. Protection of utilities may include, but is not limited to, flagging utilities, marking lines on pavement, placement of barricades along utility lines and at manholes. General Technical Provisions provide the Contractor with detailed direction for the location of underground utilities.



## 12. PENALTIES

Contractor is made aware that there may be fines assessed by BXK for violations of non-compliance to any portion of this CSPP. A schedule of assessments/fines will be provided to the Contractor prior to the beginning of construction.

BXK has the option to issue warnings on the first offense if the incident justifies it. Individuals involved in a non-compliance violation may be required to surrender their access control card and be escorted off the AOA pending investigations of the matter and the outcome of the possible appeal.

Incursions are defined as "any entrance onto an active runway, taxiway, taxilane or apron that may or may not subject any aircraft or crash fire rescue vehicle to yield, stop or change direction to avoid the sudden entrance."

#### 13. SPECIAL CONDITIONS

Special unforeseen conditions or circumstances may require the activation of special procedures by the Airport. In cases involving aircraft emergencies or distressed aircraft the Contractor may be required to temporarily halt construction activities and immediately vacate the area in which he is working. The nearest Airport Operations employee will be expected to notify all Contractor personnel in the vicinity and promote safe and orderly removal of all Contractor personnel and equipment to an area that is no longer in conflict with the emergency at hand. The Contractor will be expected to immediately comply with all Airport personnel directions and may not return to the subject work area until given the permission to do so.

In the event of low-visibility conditions, or other conditions which may signal the need for additional unimpeded space next to runways or taxiways, the Contractor may be required to move to another work area of the project or temporarily stop work. The Contractor will be made aware of the possibility of these situations during the Pre-Construction Conference.

## 14. RUNWAY & TAXIWAY VISUAL AIDS

#### 14.1 General

Temporary visual aids may be used from time to time as the project progresses to increase safety. Any temporary visual aid will be secured either in-pavement or with heavy items preventing blow-away (against jet-blast, prop wash or a 90-mph wind), while at the same time not obscuring the objects themselves.

All temporary visual aids must have frangible connections. Connections shall be submitted for approval by the Resident Engineer.

## 14.2 Markings

Any markings that may be required for this project will meet the requirements of FAA Advisory Circular 150/5340-1M, *Standards for Airport Markings*.

## 14.3 Lighting and Visual Aids

Lighting and signs for all barricades used within the AOA shall be red and shall be a steady-burn or blinking light. All barricading and lighting shall conform to the details in the plans and specifications. Low-profile barricades shall be spaced 10-ft on center and not more than 4-ft apart and shall be placed to prevent ground vehicle traffic from moving onto active airfield pavements (barring a deliberate act), and alert aircraft traffic of closed facilities.



Construction Plan Sheets **G2.02 – G2.03** show the placement of all barricades and their locations.

Lighting for any closed facilities will be disconnected or covered and secured with a material that prevents light leakage. Disconnected lighting shall be completed so as to not affect the remaining portion of facilities that may be open to aircraft traffic.

Lighting shall conform to AC 150/5340-30: Design and Installation Details for Airport Visual Aids, AC 150/5345-50: Specification for Portable Runway and Taxiway Lights, AC 150/5345-53: Airport Lighting Certification Program, AC 150/5345-44: Specification for Runway and Taxiway Signs, AC 50/5340-18: Standards for Airport Sign Systems, and AC 150/5345-53: Airport Lighting Certification Program, as required.

## **14.4 Signs**

Airfield signage illuminated to indicate an open facility that is closed due to construction shall be covered and secured with a material that prevents light leakage. Signs may be partially covered as several signs have multiple panels. In this case, only the affected panels shall be covered.

## 15. MARKING & SIGNS FOR ACCESS ROUTES

Temporary signing used for Contractor access/haul routes, open trenching or other hazards shall be clear, concise, reflective, and large enough to minimize safety-related issues. All temporary signing shall meet the requirements of the most current version of AC 150/5340-18 and, to the extent practicable, with the MUTCD and/or State highway specifications. All temporary signs shall also be properly weighted and/or secured to withstand site and elemental conditions.

#### 16. HAZARD MARKING & LIGHTING

#### 16.1 General

Hazards, such as open trenches, manholes, and steep embankments shall be barricaded and lighted with pennant flagging or orange fabric construction fencing to prohibit accidental falls. The Contractor's site-specific and company safety plan/guidelines shall address the protection of these areas and the protection of the employees against these hazards. The Contractor shall also assign a Project Safety Officer for the project to monitor and enforce the Contractor's safety guidelines and the provisions of this CSPP.

When areas on the Airport are closed or present hazards due to construction activities, they should be marked and lighted according to AC 150/5340-1M, *Standards for Airport Markings*. Marking and lighting must be approved by Airport Operations.

Some less obvious construction related hazards include, but are not limited to, the following:

- Loose debris, trash, etc. in the work areas
- Loose debris, trash, etc. on or in the bed of vehicles
- Jet blast
- Jet engine run-up noise



The Contractor shall be vigilant in keeping the work areas in a safe and trash-free condition as much as possible so as to prevent debris from making its way onto active airfield pavements. The Contractor shall also exercise due care when working the vicinity of active aircraft. This can include the use of hearing protection and the securing of clothing and hardhats while working.

#### 16.2 Barricades

#### 16.2.1 Placement

Construction areas will be barricaded with either vertical panel or low-profile barricades on aircraft movement areas. For construction areas that do not include aircraft operating areas, vertical panel barricades may be used to prohibit vehicle and pedestrian traffic. All barricades must have flashing red or steady burn lights.

Barricades, temporary markers approved by the Airport, and any other warning equipment placed or left in areas adjacent to any open aircraft movement area, (i.e. runway, taxiway, taxilane, etc.), shall be as low to the ground as possible, and not more than 18 inches in height, (unless otherwise noted on the phasing plans). All barricades and temporary markers shall also be properly secured to withstand the site and elemental conditions. All barricading requirements regarding type, spacing, etc. were provided in the plans and are further identified in the Contract Documents. Low-profile barricades shall be used and shall be reflective, have an omni-directional steady-burning or flashing red LED light, and shall be properly secured (screwed-in). Clamps or straps will not be allowed.

Low-profile barricades shall be spaced 10 feet on center and not more than 4 feet apart and shall be placed to prevent ground vehicle traffic from moving onto active airfield pavements (barring a deliberate act), and alert aircraft traffic of closed facilities.

#### 16.2.2 Lights

Red LED lights on low-profile barricades shall be of the omni-directional, flashing or steady-burn type. The rate of flash and illumination, as well as barricade reflectivity, shall meet the requirements of the latest edition of the Manual of Uniform Traffic Control Devices (MUTCD). Additional lighting shall be provided if determined necessary by Airport Operations.

#### 16.2.3 Supplement Barricades with Signs

Signage shall be installed when determined necessary by Airport Operations, i.e. "No Entry".

#### 16.2.4 Maintenance

The Contractor shall designate an employee (or Subcontractor) to be responsible for the regular maintenance of barricades and lighting. In addition, the Contractor shall provide an emergency contact number for the responsible individual to perform any emergency maintenance on any barricades or lighting and ensure functional operation of all hazard lighting and barricades 24 hours per day, 7 days per week. The designated person or subcontractor shall be able to respond to the Airport within one (1) hour of notification of a non-functioning barricade.

Barricading and lighting equipment shall be secured to prevent blow-down. This may include the use of water-filled items, sandbags, and/or flat heavy footings. Temporary lighting may be secured to the pavement with nails or screws.



# 17. WORK ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION

Lighting equipment must adequately illuminate the work area for construction performed during nighttime hours following minimum illumination levels per AC 150/5370-10H, Standard Specifications for Construction of Airports.

# 18. PROTECTION OF RSA'S, TSA'S, OFA'S, OFZ'S, AND APPROACH/DEPARTURE SURFACES

## 18.1 Runway Safety Area (RSA)

This project does not include work within the Runway '17-35' Safety Area.

## 18.2 Runway Object Free Area (ROFA)

This project does not include work within the Runway '17-35' Object Free Area.

## **18.3 Obstacle Free Zone (OFZ)**

This project does not include work within the Runway '17-35' Object Free Zone.

## 18.4 Taxiway Safety Area (TSA)

## 18.4.1 Construction Within Taxiway Safety Areas

Multiple taxiways will be affected as part of this project, and as such, any taxiway having construction within its Safety Area and Object Free Area will be closed during construction duration/hours. No equipment or tools will be left unattended within the TOFA as the Contractor will be required to move these items to the staging and storage area when not in use.

#### 18.4.2 Requirements for Open Procedures

Prior to any taxiway being reopened, the Contractor will be required to:

- Provide a sweeper truck and/or vacuum truck and clean the taxiway pavement in the vicinity of the work areas;
- Temporarily safe-up the graded/infield areas such that there are no humps, ruts, depressions, equipment, tools, or other materials within the TSA;
- Ensure that any excavation within the TSA is filled and compacted;
- Perform a FOD/safety walk of the taxiway pavement and the adjacent graded/infield areas with construction inspection and Airport staff to ensure compliance with these procedures;
- Remove the low-profile barricades from the applicable taxiways;
- Perform any additional necessary actions as a result of the FOD/safety walk as required by the construction inspection and/or Airport staff.
- Remove any barricades used for the temporary nightly closure.



#### 18.4.3 Marking of Excavations and Open Trenches

Hazards, such as open trenches, major excavations, manholes, and steep embankments shall be barricaded, lighted, and outlined with appropriate caution tape or orange fabric construction fencing to prohibit accidental falls. The Contractor's site-specific and company safety plan/guidelines shall address the protection of these areas and the protection of the employees against these hazards. See **Section 16** *Hazard Marking & Lighting* for further information.

#### 18.4.4 Blast Protection Procedures

The Contractor's company safety plan/guidelines shall include a provision for jet blast protection. At a minimum, it should address requirements for the securing of clothing and hardhats, as well as any requirements for hearing protection.

## 18.5 Taxiway Object Free Area (TOFA)

Multiple taxiways will be affected as part of this project, and as such, any taxiway having construction within its Object Free Area will be closed during construction duration/hours. No equipment or tools will be left unattended within the TOFA as the Contractor will be required to move these items to the staging and storage area when not in use. See **Section 18.4** *Taxiway Safety Area (TSA)* for further information.

## 18.6 Runway Approach & Departure Surfaces

It is not anticipated that any construction of this project will impact a Runway Approach or Departure Surface or Clearway.

## 19. OTHER LIMITATIONS ON CONSTRUCTION

#### 19.1 Prohibitions

#### 19.1.1 Use of Flare Pots

The use of flare pots is not permitted within the AOA at any time.

#### 19.1.2 Use of Electrical Blasting Caps

The use of electrical blasting caps is not permitted within 1,000-ft of the Airport property.

#### 19.2 Restrictions

#### 19.2.1 Tall Equipment

The use of tall equipment is not permitted unless a 7460-1 determination letter is issued.

#### 19.2.2 Open Flame Welding and Torches

Open flame welding and the use of torches shall be approved by the Airport prior to the project commencing. If this type of work is required on this project, the Contractor shall notify the Airport at least 48 hours in advance of the work.

## 19.2.3 Airfield Lighting Vault Lock-Out/Tag-Out Policy

This project includes installing new taxiway edge lighting in multiple areas of the project, and the contractor shall be responsible for scheduling and coordinating this work with BXK so that the appropriate lock-out/tag-out procedures are strictly adhered to.




Prior to opening any electrical pull box or light cans, the appropriate circuits will be tagged and locked out at the vault room in accordance with OSHA requirements. A pre-event meeting shall be held on site at least 48 hours in advance of the work with the Contractor, the Airport, and the Project Engineer to review the work undertaken, to familiarize all parties with the existing system and controls that will shut down and restarted, and to confirm lock-out/tag-out procedures used. The Contractor shall provide multi-position hasp and both the Contractor and BXK will attach their own separate locks. No system shall be energized until such time that both parties have removed their locks, indicating a safe situation to energize. The system will be checked for functionality by the Contractor in the presence of a BXK staff member before leaving the project site.


#### 19.2.4 Contractor Employee Safety


The Contractor and its employees shall employ safe practices per the Contractor's safety procedures and industry safety standards. The Contractor's safety procedures will ultimately dictate the use of protective clothing and equipment for its employees, but at a minimum, the Contractor's employees must be equipped with a Type 2 safety vest, and every employee that enters the site must be wearing said vest. The vest must be worn the entire time that the employee is within the AOA.




**Appendix A** Construction Phasing Plans











**Appendix B** Inspection Checklist



Item	Action Required (Describe)	No Action Required (Check)
Excavation adjacent to runways, taxiways, and aprons improperly backfilled.		
Mounds of earth, construction materials, temporary structures, and other obstacles near any open runway, taxiway, or taxi lane; in the related Object Free area and aircraft approach or departure areas/zones; or obstructing any sign or marking.		
Heavy equipment (stationary or mobile) operating or idle near AOA, in runway approaches and departures areas, or in OFZ.		
Equipment or material near NAVAIDs that may degrade or impair radiated signals and/or the monitoring of navigation and visual aids. Unauthorized or improper vehicle operations in localizer or glide slope critical areas, resulting in electronic interference and/or facility shutdown.		
Tall and especially relatively low visibility units (that is, equipment with slim profiles) — cranes, drills, and similar objects — located in critical areas, such as OFZ and approach zones.		
Improperly positioned or malfunctioning lights or unlighted airport hazards, such as holes or excavations, on any apron, open taxiway, or open taxi lane or in a related safety, approach, or departure area.		
Obstacles, loose pavement, trash, and other debris on or near AOA. Construction debris (gravel, sand, mud, paving materials) on airport pavements may result in aircraft propeller, turbine engine, or tire damage. Also, loose materials may blow about, potentially causing personal injury or equipment damage.		
Inappropriate or poorly maintained fencing during construction intended to deter human and animal intrusions into the AOA. Fencing and other markings that are inadequate to separate construction areas from open AOA create aviation hazards.		



Item	Action Required (Describe)	No Action Required (Check)
Improper or inadequate marking or lighting of runways (especially thresholds that have been displaced or runways that have been closed) and taxiways that could cause pilot confusion and provide a potential for a runway incursion. Inadequate or improper methods of marking, barricading, and lighting of temporarily closed portions of AOA create aviation hazards.		(Cireck)
Wildlife attractants — such as trash (food scraps not collected from construction personnel activity), grass seeds, tall grass, or standing water — on or near airports.		
Misleading or malfunctioning obstruction lights. Unlighted or unmarked obstructions in the approach to any open runway pose aviation hazards.		
Failure to issue, update, or cancel NOTAMs about airport or runway closures or other construction related airport conditions.		
Failure to mark and identify utilities or power cables. Damage to utilities and power cables during construction activity can result in the loss of runway / taxiway lighting; loss of navigation, visual, or approach aids; disruption of weather reporting services; and/or loss of communications.		
Lack of radio communications with construction vehicles in airport movement areas.		
Objects, regardless of whether they are marked or flagged, or activities anywhere on or near an airport that could be distracting, confusing, or alarming to pilots during aircraft operations.		
Water, snow, dirt, debris, or other contaminants that temporarily obscure or derogate the visibility of runway/taxiway marking, lighting, and pavement edges. Any condition or factor that obscures or diminishes the visibility of areas under construction.		
Spillage from vehicles (gasoline, diesel fuel, oil) on active pavement areas, such as runways, taxiways, aprons, and airport roadways.		



Item	Action Required (Describe)	No Action Required (Check)
Failure to maintain drainage system integrity during construction (for example, no temporary drainage provided when working on a drainage system).		
Failure to provide for proper electrical lockout and tagout procedures. At larger airports with multiple maintenance shifts/workers, construction contractors should make provisions for coordinating work on circuits.		
Failure to control dust. Consider limiting the amount of area from which the contractor is allowed to strip turf.		
Exposed wiring that creates an electrocution or fire ignition hazard. Identify and secure wiring and place it in conduit or bury it.		
Site burning, which can cause possible obscuration.		
Construction work taking place outside of designated work areas and out of phase		